

SUMMARY OF QUANTITIES

PAY ITEM #	DESCRIPTION	UNIT	100% STATE
			QUANTITY
67100100	MOBILIZATION	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
X0326223	FOAM, EXPANDING POLYURETHANE, HIGH-DENSITY	POUND	8,000

GENERAL NOTES

The final top 100 mm (four inches) of soil in any right-of-way area disturbed by the Contractor must be capable of supporting vegetation. The soil must be from the A horizon (zero to 2' deep) of soil profiles of local soils.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Lump Sum for MOBILIZATION.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the MOBILIZATION.

INDEX OF SHEETS

1. Cover Sheet
2. Summary of Quantities, Index of Sheets, General Notes, Standards
3. Existing Plan and Profile
4. General Plan
- 5.-9. Roadway Profiles
10. Typical Sections
11. Bridge Plan and Elevation
12. Bridge Approach Pavement Standard
13. Bridge Approach Shoulder Pavement Standard

STANDARDS

- 701101-02 Off-Road Operations, Multilane, 15' (4.5 m) to 24' (600 mm) From Pavement Edge
- 701400-05 Approach to Lane Closure, Freeway/Expressway
- 701406-06 Lane Closure, Freeway/Expressway, Day Operations Only
- 701901-01 Traffic Control Devices
- 720011-01 Metal Posts for Signs, Markers and Delineators
- 728001-01 Telescoping Steel Sign Support
- 729001-01 Applications of Types A and B Metal Posts (For Signs & Markers)

FILE NAME = C:\BR\CADD plans\Stephenson County\0890254\PLANeng.dgn	USER NAME = linkdJ	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES, STANDARDS, GENERAL NOTES, INDEX OF SHEETS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 50.0000' / IN.	CHECKED - ---	REVISED - ---	301			(18BR-1)M	STEPHENSON	13	2	
PLOT DATE = Wed Dec 08 09:02:03 2010	DATE - ---	REVISED - ---	CONTRACT NO. 64683			ILLINOIS FED. AID PROJECT				
SCALE: _____		SHEET NO. _____ OF _____ SHEETS				STA. _____ TO STA. _____				