

**GENERAL NOTES**

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF WORK; HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

EXISTING SIGNS INSTALLED IN THE AREAS OF CONCRETE MEDIAN SURFACE REMOVAL OPERATIONS SHALL BE REMOVED AND STORED AT LOCATIONS APPROVED BY THE ENGINEER SO THAT THE EXISTING SIGNS ARE NOT DAMAGED DURING THE MEDIAN REMOVAL AND REPLACEMENT OPERATIONS. WHEN THE CONCRETE MEDIAN IS RECONSTRUCTED, THE CONTRACTOR SHALL INSTALL BLOCKOUTS AT EXISTING SIGN LOCATIONS TO AID IN THE RE-INSTALLATION OF EXISTING SIGNS. COST SHALL BE INCLUDED IN THE "CONCRETE MEDIAN SURFACE" WORK.

**COMMITMENTS**

NONE 10/26/2010

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DISTRICT THREE

PREPARED BY: *David Broviak*  
DISTRICT STUDIES & PLANS ENGINEER

DATE: 12-21-10

EXAMINED BY: *Herbert Long*  
DISTRICT CONSTRUCTION ENGINEER

*Ray J. Peltz*  
DISTRICT MATERIALS ENGINEER

*Benjamin A. Hatcher*  
DISTRICT OPERATIONS ENGINEER

FILE NAME *	USER NAME = woodshankr1	DESIGNED - RLW	REVISED - -----
c:\pw_work\pwidot\woodshankr1\d0143164	MAIN1-0366A27-details.dgn	DRAWN - RLW	REVISED - -----
	PLOT SCALE = 100.0000 / IN.	CHECKED - ---	REVISED - -----
	PLOT DATE = Dec 15, 2010 - 11:05:49 AM	DATE - -----	REVISED - -----

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE: \_\_\_\_\_ SHEET NO. 1 OF 1 SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2370	(78-1HB-1)	PUTNAM	18	2
CONTRACT NO. 66A27				
ILLINOIS FED. AID PROJECT				