

SCHEDULE FOR MEDIAN REPAIR

LOCATION				COMBINATION CONCRETE CURB AND GUTTER REMOVAL	CONCRETE MEDIAN SURFACE REMOVAL	SUB-BASE GRANULAR MATERIAL TYPE B 4"	COMBINATION CONCRETE CURB AND GUTTER TYPE B-9.12	CONCRETE MEDIAN SURFACE 4"
STATION	TO	STATION	NB/SB	FEET	SO FT	SO YD	FOOT	SO FT
STA. 37+19	TO	STA. 37+47	SB	28	80	9	28	80
STA. 37+41	TO	STA. 37+47	NB	6			6	
STA. 38+23	TO	STA. 38+34	SB	11	31	3	11	31
STA. 38+23	TO	STA. 38+34	NB	11			11	
STA. 38+58	TO	STA. 38+64	SB	6	17	2	6	17
STA. 41+02	TO	STA. 41+06		4	11	1	4	11
STA. 41+35	TO	STA. 41+39		4	11	1	4	11
STA. 41+39	TO	STA. 42+78	SB	139	395	44	139	395
STA. 41+39	TO	STA. 42+78	NB	139	395	44	139	395
TOTAL				348	940	104	348	940