

LOCATION OF WORK:

FAI 74
RURAL
INTERSTATE
MCLEAN COUNTY
STA. 737+00 TO STA. 1111+00
E OF US 51 TO CH 36 AT DOWNS

FUNDING BREAKOUT:
CONSTRUCTION TYPE CODE:

90% FEDERAL / 10% STATE
0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	280.0
20400800	FURNISHED EXCAVATION	CU YD	600.0
21400100	GRADING AND SHAPING DITCHES	FOOT	1,025.0
* 25000210	SEEDING, CLASS 2A	ACRE	3.0
* 25000350	SEEDING, CLASS 7	ACRE	3.0
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	270.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	270.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	270.0
* 25100115	MULCH, METHOD 2	ACRE	6.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300.0
28000305	TEMPORARY DITCH CHECKS	FOOT	325.0
28000500	INLET AND PIPE PROTECTION	EACH	20.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	530.0
28200200	FILTER FABRIC	SQ YD	530.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	33,000.0
40600300	AGGREGATE (PRIME COAT)	TON	655.0
40600895	CONSTRUCTING TEST STRIP	EACH	3.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,800.0
40600990	TEMPORARY RAMP	SQ YD	1,600.0
40603244	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N105	TON	21,800.0

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = hoganbj	DESIGNED - BJH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\pripdot\hoganbj\d0158340\0570550-sh1-500.dgn	DRAWN - BJH 10/12/2010	REVISED -						74	(57-2011),21,22)RS-3	MCLEAN	150	7
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			SCALE: _____	SHEET NO. 1 OF 7 SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 70550				
PLOT DATE = 10/20/2010	DATE -	REVISED -			ILLINOIS FED. AID PROJECT							