

SCHEDULES OF QUANTITIES

CLASS A PATCHES, 7"

STATION I-74	DIRECTION	LANE DRIVING	LENGTH (ft)	WIDTH (ft)	PATCH AREA				SAW CUTS (ft)	TIE BARS 3/4" (each)	PATCHING REINFORCEMENT 44213000 (sq yd)
					TYPE I 7.0" 44200513 (sq. yd)	TYPE II 7.0" 44200517 (sq. yd)	TYPE III 7.0" 44200521 (sq. yd)	TYPE IV 7.0" 44200523 (sq. yd)			
					1090+00	EB	DL	50			
1109+10	EB	DL	10	12	0.0	13.3	0.0	0.0	68	0	13.3
777+08	WB	DL	10	6	0.0	6.7	0.0	0.0	44	0	6.7
779+30	WB	DL	100	6	0.0	0.0	0.0	66.7	224	50	66.7
783+30	WB	DL	10	12	0.0	13.3	0.0	0.0	68	0	13.3
832+15	WB	DL	25	12	0.0	0.0	0.0	33.3	98	13	33.3
869+69	WB	DL	6	6	4.0	0.0	0.0	0.0	36	0	4
980+25	WB	DL	10	12	0.0	13.3	0.0	0.0	68	0	13.3
1111+00	WB	DL	12	12	0.0	0.0	16.0	0.0	72	0	16
CLASS A PATCH, 7" TOTAL:					4.0	46.6	16.0	166.7	826	88	233.3
ROUND TO:					5	50	20	170	830	90	245

CLASS A PATCHES, 13"

STATION I-74	DIRECTION	LANE	LENGTH	WIDTH	PATCH AREA				SAW CUTS (ft)	TIE BARS 3/4" (each)	PATCHING REINFORCEMENT 44213000 (sq yd)
					TYPE I	TYPE II 13.0" 44200610 (sq. yd)	TYPE III	TYPE IV 13.0" 44200614 (sq. yd)			
					838+80	WB	PL	10			
980+25	WB	PL	10	12	0.0	13.3	0.0	0.0	68	0	13.3
1109+77	WB	PL	6	12	0.0	8.0	0.0	0.0	60	0	8.0
1111+00	WB	PL	10	12	0.0	13.3	0.0	0.0	68	0	13.3
1090+00	EB	PL	50	12	0.0	0.0	0.0	66.7	148	25	66.7
CLASS A PATCH, 13" TOTAL:					0.0	47.9	0.0	66.7	412	25	114.6
ROUND TO:						50		70	420	25	120

CLASS A PATCH GRAND TOTAL:					1250	115	365
-----------------------------------	--	--	--	--	------	-----	-----