

SCHEDULES OF QUANTITIES

CLASS D PATCHES, 10" CONTINUED

STATION CH 36	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA			
					TYPE I 10.0" (sq. yd)	TYPE II 10.0" 44201765 (sq. yd)	TYPE III 10.0" 44201769 (sq. yd)	TYPE IV 10.0" 44201771 (sq. yd)
					56+63	SB	DL	4
59+37	SB	DL	6	14	0.0	9.3	0.0	0.0
60+37	SB	DL	4	14	0.0	6.2	0.0	0.0
60+79	SB	DL	4	14	0.0	6.2	0.0	0.0
61+38	SB	DL	4	14	0.0	6.2	0.0	0.0
62+41	SB	DL	6	14	0.0	9.3	0.0	0.0
63+40	SB	DL	6	14	0.0	9.3	0.0	0.0
64+43	SB	DL	6	14	0.0	9.3	0.0	0.0
65+30	SB	DL	6	14	0.0	9.3	0.0	0.0
66+34	SB	DL	6	14	0.0	9.3	0.0	0.0
67+36	SB	DL	6	14	0.0	9.3	0.0	0.0
68+00	SB	DL	6	14	0.0	9.3	0.0	0.0
68+75	SB	DL	6	14	0.0	9.3	0.0	0.0
69+25	SB	DL	4	12	0.0	5.3	0.0	0.0
CLASS D PATCH, 10" TOTALS:						706.8	124.4	202.2
ROUND TO:						710	125	205

AGGREGATE WEDGE SHOULDER, TYPE B

LOCATION	STA.	TO	STA.	# OF SIDES	AVE DEPTH (IN)	LENGTH (FT)	WIDTH (FT)	AGGREGATE WEDGE SHOULDER, TYPE B 48102100 (TON)
WB & EB SHLDS	737+00		779+38	4	1.9	4,238.5	3.0	536.9
WB & EB SHLDS	781+58		1037+74	4	1.9	25,615.9	3.0	3,244.7
WB & EB SHLDS	1040+25		1111+00	4	1.9	7,074.8	3.0	896.1
RAMP AC - WB ON	10+24		31+64	2	1.9	2,140.1	3.0	135.5
RAMP DA - WB OFF	10+00		27+60	2	1.9	1,760.5	3.0	111.5
RAMP CB - EB OFF	10+00		28+64	2	1.9	1,864.0	3.0	118.1
RAMP BD - EB ON	10+24		32+79	2	1.9	2,255.3	3.0	142.8
CROSS OVERS	VAR		VAR	6	1.9	73.1	3.0	13.9
C.H. 36	16+92		48+85	2	1	3,192.5	3.0	106.4
C.H. 36	51+15		68+96	2	1	1,781.0	3.0	59.4
C.H. 36	69+06		69+50	2	1	44.0	3.0	1.5
TOTAL =								5,366.7
ROUND TO:								5,400

TONNAGE = (((AVE D" / 12 IN/FT) X LENGTH' X WIDTH') / (27 CF/CY)) X (# SIDES) X (1.8 TONS/CY)

PARTIAL DEPTH PATCHES

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	EXISTING HMA OVERLAY THICKNESS (inch)	PD PATCHING (SPECIAL) X0556100 (sq yd)	ESTIMATED HMA QUANTITY * (ton)
EB OFF-RAMP "CB"							
16+40	EB		4	16	0.0	7.1	1.2
16+62	EB		4	16	0.0	7.1	1.2
18+57	EB		4	16	0.0	7.1	1.2
20+50	EB		4	16	0.0	7.1	1.2
25+57	EB		4	16	0.0	7.1	1.2
26+63	EB		4	16	0.0	7.1	1.2
27+68	EB		6	16	0.0	10.7	1.8
EB ON-RAMP "BD"							
10+60	EB		4	16	0.0	7.1	1.2
12+50	EB		4	16	0.0	7.1	1.2
14+56	EB		4	16	0.0	7.1	1.2
16+10	EB		4	16	0.0	7.1	1.2
16+25	EB		4	16	0.0	7.1	1.2
16+77	EB		4	16	0.0	7.1	1.2
18+58	EB		4	16	0.0	7.1	1.2
WB OFF-RAMP "DA"							
16+07	WB		4	16	0.0	7.1	1.2
26+55	WB		4	16	0.0	7.1	1.2
26+90	WB		40	4	0.0	17.8	3.0
27+25	WB		30	6	0.0	20.0	3.4
WB ON-RAMP "AC"							
11+10	WB		6	18	0.0	12.0	2.0
CH 36							
20+50	NB	D	4	12	2.5	5.3	1.6
23+50	NB	D	4	12	2.5	5.3	1.6
20+50	SB	D	4	12	2.5	5.3	1.6
23+50	SB	D	4	12	2.5	5.3	1.6
PARTIAL DEPTH PATCH TOTALS:						188.2	34.6
ROUND TO:						190	

*THIS QUANTITY IS FOR INFORMATION ONLY. THE COST OF THE HOT-MIX ASPHALT SHALL BE INCLUDED WITH THE PARTIAL DEPTH PATCHING (SPECIAL) PAY ITEM WITH NO ADDITIONAL COMPENSATION ALLOWED.