

SUMMARY OF QUANTITIES

LOCATION OF WORK:

EDGAR CO.
FAP 91 (US 150)
RURAL TWO-LANE
MINOR STRUCTURE REPAIR

EDGAR CO.
FAP 332 (US 150 / IL 1)
URBAN TWO-LANE
MINOR STRUCTURE REPAIR

STRUCTURE NUMBER:
FUNDING BREAKOUT:
CONSTRUCTION TYPE CODE:

023-0013
100% STATE

023-0024
100% STATE

0014

0014

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	73.0	73.0	
50102400	CONCRETE REMOVAL	CU YD	9.9		9.9
50300100	FLOOR DRAINS	EACH	34.0	34.0	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	9.9		9.9
50300300	PROTECTIVE COAT	SQ YD	29.0		29.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	880.0		880.0
50800515	BAR SPLICERS	EACH	10.0		10.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	68.0		68.0
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	899.0	899.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1.0	0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0	1.0	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.5	0.5
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2.0	1.0	1.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	309.0	212	97.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	325.0		325.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	325.0		325.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,237.0	850.0	387.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	7.0	7.0	
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	7.0	7.0	
X5080600	MECHANICAL SPLICERS	EACH	10.0		10.0
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0		1.0
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	26.0		26.0
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	870.0	870.0	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	179.0	179.0	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	130.0	130.0	
Z0021908	SILICONE JOINT SEALER, 2"	FOOT	41.0	41.0	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2.0		2.0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2.0		2.0

* SPECIALTY ITEMS

FILE NAME =	USER NAME = carroll-t	DESIGNED -	REVISED -
at:\pwork\pvidot\carroll-t\d0212107\057873-shi-cover.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 12/10/2010		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

*91 & 332

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	101 BDR & CX-BJR	EDGAR	36	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 70873	