

SCHEDULE OF QUANTITIES

CROSS SECTION	LOCATION	STA.	TO	STA.	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) 40600100 GALLONS	SHORT TERM PAVEMENT MARKING 70300100 FOOT	WORK ZONE PAVEMENT MARKING REMOVAL 70301000 SQ FT	EPOXY PAVEMENT MARKING - LINE 4" 78005110 FOOT	RAISED REFLECTIVE PAVEMENT MARKER 78100100 EACH	
1	EB	909+55.00		921+03.15	1,148.1	3.0	382.7	38.3	114.8	38.3	287.0	14.4	
	(SN 074-0037)	921+03.15		924+07.75									
1	EB	924+07.75		1058+10.00	13,402.3	3.0	4,467.4	446.7	1340.2	446.7	3350.6	167.5	
1	WB	910+03.00		921+44.98	1,142.0	5.0	634.4	63.4	159.9	53.3	1427.5	14.3	
	(SN 074-0038)	921+44.98		924+55.69									
1	WB	924+55.69		1056+78.00	13,222.3	5.0	7,345.7	734.6	1851.1	617.0	16527.9	165.3	
2	FAP 721	29+25.00		44+59.00	1,534.0	2.0	340.9	34.1	153.4	51.1	383.5	19.2	
2	FAP 721	57+48.70		60+59.40	310.7	2.0	69.0	6.9	31.1	10.4	77.7	3.9	
2	FAP 721	76+72.00		92+50.00	1,578.0	2.0	350.7	35.1	157.8	52.6	394.5	19.7	
3	FAP 721	44+59.00		57+48.70	1,289.7	2.0	286.6	28.7	129.0	43.0	322.4	16.1	
3	FAP 721	60+59.40		76+72.00	1,612.6	2.0	358.4	35.8	161.3	53.8	403.2	20.2	
								TOTAL	1,423.6	4,098.5	1,366.2	23,174.2	440.5
								ROUND	1,450.0	4,150.0	1,450.0	23,200.0	500.0

CROSS SECTION	LOCATION	STA.	TO	STA.	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ YD)	PAVEMENT MARKING REMOVAL 78300100 SQ FT	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL 78300200 EACH	FIBER ASPHALT Z0004005 POUND	MICRO-SURFACING, SINGLE PASS, TYPE II Z0063805 SQ YD	
1	EB	909+55.00		921+03.15	1,148.1	3.0	382.7	95.7	14.4	470.7	382.7	
	(SN 074-0037)	921+03.15		924+07.75								
1	EB	924+07.75		1058+10.00	13,402.3	3.0	4,467.4	1116.9	167.5	5494.9	4467.4	
1	WB	910+03.00		921+44.98	1,142.0	5.0	634.4	475.8	14.3	936.4	634.4	
	(SN 074-0038)	921+44.98		924+55.69								
1	WB	924+55.69		1056+78.00	13,222.3	5.0	7,345.7	5509.3	165.3	10842.3	7345.7	
2	FAP 721	29+25.00		44+59.00	1,534.0	2.0	340.9	127.8	19.2	628.9	340.9	
2	FAP 721	57+48.70		60+59.40	310.7	2.0	69.0	25.9	3.9	127.4	69.0	
2	FAP 721	76+72.00		92+50.00	1,578.0	2.0	350.7	131.5	19.7	647.0	350.7	
3	FAP 721	44+59.00		57+48.70	1,289.7	2.0	286.6	107.5	16.1	528.8	286.6	
3	FAP 721	60+59.40		76+72.00	1,612.6	2.0	358.4	134.4	20.2	661.2	358.4	
								TOTAL	7,724.7	440.5	20,337.6	14,235.9
								ROUND	7,750.0	500.0	20,400.0	14,350.0

FILE NAME =	USER NAME = berganAJ	DESIGNED - AJB 11/24/2010	REVISED -
ct:\pw\work\p\d\berganAJ\0243642\0570890-sh-t-schedule.CEL		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/13/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
***	(74-2) & (113) I	**	15	10
CONTRACT NO. 70890			ILLINOIS FED. AID PROJECT	

** DEWITT & PIATTT
*** F.A.I. 74 & F.A.P. 721