ENTRANCE SCHEDULE

LOCATION FAP 753 (IL 104)	EXIST. SURF. TYPE	WIDTH ACROSS FRONT (FT)	WIDTH ACROSS BACK (FT)	LENGTH OF IMPROVEMENT FROM EOP (FT)	HOT-MIX ASPH. SURF. REMOVAL BUTT-JOINT (SQ YD)	INCIDENTAL HOT-MIX ASPH. SURF. (TON)	BITUMINOUS MATERIAL (PRIME COAT) (TON)	AGGREGATE SURF. CSE. TYPE B (TON)
CE LT. STA. 227+40 .00	HMA / AGG	32	23	6	18.3	2.1	0.01	2.3
PE LT. STA. 231+00.00	HMA / AGG	71	63	4	29.8	3.5	0.01	6.0
PE LT. STA. 236+40.00	HMA	38	26	4	14.4	1.7	0.01	2.5
PE W/MBT RT. STA. 312+50.00	HMA / AGG	67	42	4	24.4	2.8	0.01	4.0
PE RT. STA. 319+80.00	HMA	27	15	4	9.4	1.1	0.01	1.5
PE W/MBT RT. STA. 320+30.00	HMA	56	16	11	44.0	5.0	0.02	1.5
PE RT. STA. 321+40.00	HMA	23	9	11	19.6	2.2	0.01	1.0
PE W/MBT RT. STA. 322+30.00	HMA / AGG	48	17	11	39.8	4.5	0.02	1.7
PE LT. STA. 332+00.00	HMA	26	21	11	28.8	3.3	0.01	2.0
PE RT. STA. 333+30.00	HMA / AGG	26	21	11	28.8	3.3	0.01	2.0
PE LT. STA. 385+30.00	BIT / AGG	32	26	4	12.9	1.5	0.01	2.5
PE LT. STA. 386+10.00	BIT / AGG	25	19	4	9.8	1.1	0.01	2.0
				TOTAL	280.0	32.0	0.15	29.0

SHOULDER RUMBLE STRIP SCHEDULE

LOCATION STATION TO STATION	SHOULDERS	TOTAL LENGTH (FT)	LENGTH (FT)
FAP 753 (IL 104)			
LT.STA. 164+54.00 TO LT.STA. 193+33.46	EXIST.	2,879.5	2,823.5
RT.STA. 164+54.00 TO RT.STA. 193+33.46	EXIST.	2,879.5	2,879.5
BRIDGE OMISSION STA. 193+33.46 TO STA. 197+21.23			
LT.STA. 197+21.23 TO LT.STA. 217+43.00	EXIST.	2,022.0	1,959.0
RT.STA. 197+21.23 TO RT.STA. 217+72.00	EXIST.	2,051.0	2,004.0
OMISSION LT. STA. 217+43.00 TO LT. STA. 225+24.00			
OMISSION RT. STA. 217+72.00 TO RT. STA. 225+24.00			
LT.STA. 225+24.00 TO LT.STA. 227+49.00	PROP.	225.0	194.0
RT.STA. 225+24.00 TO RT.STA. 227+49.00	PROP.	225.0	225.0
LT.STA. 227+49.00 TO LT.STA. 230+11.00	PROP.	262.0	262.0
RT.STA. 227+49.00 TO RT.STA. 230+11.00	PROP.	262.0	262.0
LT.STA. 230+11.00 TO LT.STA. 413+02.00	PROP.	18,291.0	17,737.0
LT.STA. 413+02.00 TO LT.STA. 414+45.00	PROP.	143.0	143.0
RT.STA. 230+11.00 TO RT.STA. 414+45.00	PROP.	18,434.0	17,691.0
	TOTAL	**47,674.0**	**46,180.0**

AGGREGATE SHOULDERS, TYPE B SCHEDULE

LOCATION STATION TO STATION	AGGREGATE SHOULDERS, WIDTH (FT)	TOTAL LENGTH (FT)	LENGTH (FT)	AGGREGATE SHOULDERS, TYPE B (TON)
FAP 753 (IL 104)				
LT.STA. 225+24.00 TO LT.STA. 227+49.00	3	225	225.0	13.0
RT.STA. 225+24.00 TO RT.STA. 227+49.00	3	225	225.0	13.0
LT.STA. 227+49.00 TO LT.STA. 230+11.00	3	262	262.0	15.0
RT.STA. 227+49.00 TO RT.STA. 230+11.00	3	262	262.0	15.0
LT.STA. 230+11.00 TO LT.STA. 408+00.00	3	17,789.0	17,600.0	1002.2
LT.STA. 413+02.00 TO LT.STA. 414+45.00	3	143.0	143.0	8.0
RT.STA. 230+11.00 TO RT.STA. 414+45.00	3	18,434.0	18,080.0	1029.8
	TOTAL	**37,340.0**	**36,797.0**	**2,096.0**