

PAVING SCHEDULE			LENGTH	PAVEMENT WIDTH	SHOULDER WIDTH	AREA	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL (BUTT-JOINT)	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	LEVELING BINDER (MACHINE METHOD), NTO	HOT MIX ASPHALT SURFACE COURSE, MIX "C", NTO	HOT MIX ASPHALT BINDER COURSE, IL-19.0, NTO	INCIDENTAL HOT-MIX ASPHALT SURFACING	HOT-MIX ASPHALT SHOULDERS
STATION	TO	STATION	FEET	FEET	FEET	SQ YD	TON	GALLON	TON	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON	TON	TON
0+12.00	TO	2+86.56	274.6	42.0	0.0	1,281.3	0.0	128.1	2.6	0.0	1310.7	0.0	0.0	53.8	110.1	0.0	0.0	0.0
2+86.56	TO	3+18.50	31.9	Variable	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
3+18.50	TO	4+00.41	81.9	Variable	0.0	618.4	0.0	61.8	1.2	0.0	618.4	0.0	0.0	26.0	51.9	0.0	0.0	0.0
4+00.41	TO	21+55.05	1,754.6	42.0	0.0	8,188.3	0.0	1,161.8	23.4	0.0	11631.9	0.0	0.0	486.9	976.3	0.0	30.7	0.0
21+55.05	TO	21+92.30	37.3	42.0	0.0	173.8	0.0	17.4	0.3	0.0	173.8	0.0	0.0	7.3	14.6	0.0	0.0	0.0
21+92.30	TO	22+40.19	47.9	26.0	0.0	138.3	0.0	0.0	0.3	0.0	0.0	0.0	0.0	0.0	11.6	0.0	0.0	0.0
22+40.19	TO	75+36.00	5,295.8	26.0	15.0	15,299.0	1150.3	1,529.9	30.6	0.0	0.0	0.0	15464.0	642.6	1,299.0	0.0	51.6	0.0
75+36.00	TO	94+60.00	1,924.0	24.0	20.0	5,130.7	638.2	513.1	10.3	0.0	5130.7	0.0	0.0	215.5	431.0	0.0	13.9	0.0
94+60.00	TO	109+69.00	1,509.0	26.0	6.0	4,359.3	330.6	435.9	8.7	0.0	0.0	0.0	4359.3	183.1	366.2	0.0	0.0	0.0
109+69.00	TO	116+53.00	684.0	24.0	6.0	1,824.0	126.3	182.4	3.6	0.0	1824.0	0.0	0.0	76.6	153.2	0.0	0.0	0.0
116+53.00	TO	222+47.00	10,584.0	26.0	6.0	30,576.0	772.3	3,057.6	61.2	0.0	0.0	0.0	30576.0	1284.2	2,568.4	0.0	117.0	0.0
222+47.00	TO	223+17.00	70.0	26.0	6.0	202.2	5.4	20.2	0.4	0.0	0.0	0.0	202.2	8.5	17.0	0.0	7.4	0.0
223+17.00	TO	233+80.53	1,063.5	26.0	6.0	3,072.4	68.6	307.2	6.1	0.0	0.0	3072.4	0.0	172.1	258.1	0.0	0.0	0.0
233+80.53	=	234+37.80	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
234+37.80	TO	236+33.27	195.5	26.0	6.0	564.7	15.1	56.5	1.1	0.0	0.0	564.7	0.0	31.6	47.4	0.0	0.0	0.0
236+33.27	TO	237+03.27	70.0	26.0	6.0	202.2	5.4	20.2	0.4	0.0	0.0	0.0	202.2	8.5	17.0	0.0	0.0	0.0
237+03.27	TO	237+80.00	76.7	26.0	0.0	221.7	3.9	22.2	0.4	0.0	0.0	0.0	221.7	9.3	18.6	0.0	0.0	0.0
237+80.00	TO	268+52.31	3,072.3	26.0	6.0	8,875.6	228.5	887.6	17.8	0.0	0.0	0.0	8875.6	372.8	745.5	0.0	18.0	0.0
268+52.31	=	269+14.40	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
269+14.40	TO	283+52.00	1,437.6	26.0	6.0	4,153.1	103.4	415.3	8.3	0.0	0.0	0.0	4153.1	174.4	348.9	0.0	8.1	0.0
283+52.00	TO	290+97.00	745.0	24.0	0.0	1,986.7	0.0	198.7	4.0	0.0	1986.7	0.0	0.0	83.4	166.9	0.0	0.0	0.0
290+97.00	TO	301+00.00	1,003.0	26.0	6.0	2,897.6	69.5	289.8	5.8	0.0	0.0	0.0	2897.6	121.7	243.4	0.0	0.0	0.0
301+00.00	TO	314+03.00	1,303.0	24.0	0.0	3,474.7	0.0	347.5	6.9	0.0	3474.7	0.0	0.0	145.9	291.9	0.0	0.0	0.0
314+03.00	TO	358+94.00	4,491.0	26.0	6.0	12,974.0	312.8	1,297.4	25.9	0.0	0.0	0.0	12974.0	544.9	1,089.8	0.0	33.7	0.0
358+94.00	TO	369+55.00	1,061.0	24.0	0.0	2,829.3	0.0	282.9	5.7	0.0	2829.3	0.0	0.0	118.8	237.7	0.0	0.0	0.0
369+55.00	TO	375+40.00	585.0	26.0	6.0	1,690.0	40.3	169.0	3.4	0.0	0.0	0.0	1690.0	71.0	142.0	0.0	3.5	0.0
375+40.00	=	100+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
99+00.00	TO	100+00.00	100.0	24.0	4.0	266.7	20.7	26.7	0.5	0.0	0.0	0.0	0.0	14.9	22.4	0.0	0.0	0.0
65+60.00	TO	99+00.00	3,340.0	24.0	4.0	8,906.7	207.4	1,261.8	25.2	171.0	0.0	0.0	0.0	498.8	748.2	0.0	10.2	182.0
NEW HOPE RD.																		
53+89.00	TO	54+87.30	98.3	Variable	4.0	330.5	5.0	33.1	0.7	64.9	0.0	0.0	0.0	0.0	27.8	209.4	0.0	0.0
SHEET TOTALS			37,399			120,237	4,104	12,724	255	236	28,980	3,637	81,616	5,353	10,405	209	294	182

FILE NAME = c:\pwwork\pwwork\swartzw\d0177935\d77448-sht-sch.dgn
 USER NAME = swartzw
 DESIGNED -
 DRAWN -
 CHECKED -
 PLOT SCALE = 50,0000' / IN.
 PLOT DATE = 12/27/2010

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 SCALE: NA SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE. 328 SECTION 104 RS-4 COUNTY WAYNE TOTAL SHEETS 77 SHEET NO. 12 CONTRACT NO. 74448 ILLINOIS FED. AID PROJECT