

TEMPORARY RAMP, SPECIAL SCHEDULE

LOCATION			WIDTH FEET	LENGTH FEET	AREA SQ YD
RT. 1+21.42	CE	0+00.00	2.0	44.0	9.8
LT. 1+50.61	ALLEY	0+00.00	2.0	24.0	5.3
LT. 2+28.70	CE	0+00.00	2.0	31.0	6.9
RT. 3+65.40	SIDEWALK	0+00.00	2.0	5.0	1.1
LT. 3+81.40	PE	0+00.00	2.0	29.0	6.4
RT. 4+22.21	CE	0+00.00	2.0	40.0	8.9
LT. 5+03.56	PE	0+00.00	2.0	30.5	6.8
RT. 5+42.96	ALLEY	0+00.00	2.0	28.0	6.2
RT. 6+08.01	PE	0+00.00	2.0	14.0	3.1
LT. 6+20.66	PE	0+00.00	2.0	22.0	4.9
LT. 8+47.41	CE	0+00.00	2.0	80.0	17.8
LT. 9+05.76	CE	0+00.00	2.0	33.0	7.3
RT. 9+11.98	PE	0+00.00	2.0	32.0	7.1
RT. 9+66.06	ALLEY	0+00.00	2.0	29.0	6.4
LT. 9+68.89	ALLEY	0+00.00	2.0	26.0	5.8
RT. 10+36.26	PE	0+00.00	2.0	20.0	4.4
LT. 13+41.31	ALLEY	0+00.00	2.0	28.0	6.2
LT. 13+96.51	ALLEY	0+00.00	2.0	20.0	4.4
RT. 13+98.10	ALLEY	0+00.00	2.0	21.0	4.7
RT. 15+03.61	PE	0+00.00	2.0	21.0	4.7
LT. 17+38.61	PE	0+00.00	2.0	21.0	4.7
RT. 17+64.57	ALLEY	0+00.00	2.0	45.0	10.0
LT. 17+78.26	CE	0+00.00	2.0	30.0	6.7
LT. 18+17.46	CE	0+00.00	2.0	32.0	7.1
RT. 18+57.64	PE	0+00.00	2.0	20.0	4.4
LT. 18+75.53	CE	0+00.00	2.0	50.0	11.1
LT. 19+64.14	CE	0+00.00	2.0	35.0	7.8
RT. 20+02.39	CE	0+00.00	2.0	45.0	10.0
LT. 20+03.20	CE	0+00.00	2.0	35.0	7.8
RT. 21+31.72	CE	0+00.00	2.0	40.0	8.9
TOTAL =					207

SURVEY MONUMENT COVER ASSEMBLY SCHEDULE

LOCATION	TYPE	QUANTITY EACH	DESCRIPTION
133+75.00	SEC. CORNR	1.0	17.2' LT. STA. 133+75, IP, CL OF TR650N
TOTAL =		1.0	

CONCRETE MEDIAN SURFACE REMOVAL SCHEDULE

LOCATION	AREA SQ FT	DESC.
03+26.43 RT. 29.75'	46.7	ISLAND
TOTAL =		46.7

PATCHING SCHEDULE

LOCATION	CLASS B PATCHES, TYPE I, 8"	CLASS B PATCHES, TYPE II, 8"	CLASS B PATCHES, TYPE IV, 8"	CLASS D PATCHES, TYPE I, 13"	CLASS D PATCHES, TYPE II, 13"	CLASS D PATCHES, TYPE III, 13"	CLASS D PATCHES, TYPE IV, 13"	PARTIAL DEPTH PATCHING (SPECIAL)	PARTIAL DEPTH REMOVAL, 3"	PARTIAL DEPTH PATCHING	HOT-MIX ASPHALT FOR PATCHING
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON
FAP328 (US 45)	21	232	380	8	643	132	120	940	308	52	368

TEMPORARY RAMPS SCHEDULE

LOCATION	LENGTH FEET	WIDTH FEET	AREA SQ YD	
0+12.00	BEGINNING OF PROJECT	7.5	58.8	49.0
2+86.57	N. INT. OF US 45/EB IL 15	7.5	70.1	58.4
3+18.50	S. INT. OF US 45/EB IL 15	7.5	80.4	67.0
3+33.50	RT. TURN LN, 76.5' RT.	7.5	VAR.	13.0
21+92.30	N. EDGE OF PRECAST RR XING	7.5	42.0	35.0
22+40.19	S. EDGE OF PRECAST RR XING	5.0	42.0	23.3
65+10.00	END OF PROJECT	5.0	44.0	24.4
TOTAL =			270	

PERMANENT SURVEY MARKER, TYPE 1 SCHEDULE

LOCATION	TYPE	QUANTITY EACH	DESCRIPTION
202+32.88	CL POT	1.0	
225+12.04	CL PC	1.0	
233+80.53	CL PT	1.0	STA. EQ. 233+80.53 BK=234+37.80 AH
259+75.07	CL PC	1.0	
264+50.00	CL POT	1.0	
268+52.31	CL PT	1.0	STA. EQ. 268+52.31 BK=269+14.40 AH
284+69.53	CL POT	1.0	
TOTAL =		7.0	

CURB REMOVAL SCHEDULE

LOCATION	LENGTH (FEET)	DESC.
03+26.43 RT. 29.75'	34.7	ISLAND
TOTAL =		34.7