

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0021 100% STATE		
35300505	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/4"	SO YD	12	12		
44003100	MEDIAN REMOVAL	SO FT	108	108		
67100100	MOBILIZATION	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
<del>70102620</del>	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
*72000300	SIGN PANEL - TYPE 3	SO FT	78	78		
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	183	183		
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	133	133		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	72	72		
78300100	PAVEMENT MARKING REMOVAL	SO FT	92	92		
80500100	SERVICE INSTALLATION, TYPE A	EACH	1	1		
81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC	FOOT	15	15		
81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	571	571		
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	301	301		
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	42	42		
81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	197	197		
81400100	HANDHOLE	EACH	5	5		
81400300	DOUBLE HANDHOLE	EACH	1	1		
81500100	GULFBOX JUNCTION	EACH	4	4		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	929	929		
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1		
86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1	1		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1426	1426		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	588	588		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1715	1715		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	27	27		
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	1	1		
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	1	1		
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1	1		
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1	1		

\* SPECIALTY ITEM

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0021 100% STATE		
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1	1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6	6		
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3.5	3.5		
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30	30		
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4	4		
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	5	5		
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1	1		
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1	1		
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	12	12		
88500100	INDUCTIVE LOOP DETECTOR	EACH	10	10		
88600100	DETECTOR LOOP, TYPE I	FOOT	788	788		
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	408	408		

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILEL*		DRAWN -	REVISED -					1809	(22)TS-1	LAWRENCE	12	3
	PLOT SCALE = *SCALE*	CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE = *DATE*	DATE -	REVISED -		CONTRACT NO. 74480							