

EROSION CONTROL SCHEDULE

STATION	OFFSET	STATION	OFFSET	PERMANENT							TEMPORARY								
				SEEDING, CLASS 2A (ACRE)	EROSION CONTROL BLANKET (SQ YD)	MULCH METHOD 2 (ACRE) *	POTASSIUM FERTILIZER NUTRIENT (POUND)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHOROUS FERTILIZER NUTRIENT (POUND)	STONE RIPRAP, CLASS A3 (SQ YD)	FILTER FABRIC (SQ YD)	TEMPORARY EROSION CONTROL SEEDING (POUND)	PERIMETER EROSION BARRIER (FOOT)	INLET AND PIPE PROTECTION (EACH)	INLET FILTERS (EACH)	TREE TRUNK PROTECTION (EACH)	TEMPORARY DITCH CHECKS (FOOT)		
IL 13/15																			
133+85.3	MEDIAN	133+16.7	MEDIAN	0.04	210.8														
136+79.0	LT	139+22.0	LT	0.63	3,024.6	3	112.5	112.5	112.5	250									
140+51.4	LT	145+30.0	LT																
136+79.0	RT	139+46.6	RT	0.18	869.7														
140+24.9	RT	142+70.4	RT	0.25	1,213.2														
137+00.0	LT	139+40.9	LT																
140+33.3	LT	140+84.0	LT								672.3	672.3							
											127.9	127.9							
136+81.0	22.9 LT	136+81.0	72.2 LT												49.3				
136+81.0	72.2 LT	139+37.0	75.2 LT												256.0				
140+40.0	81.0 LT	141+66.0	47 LT												130.5				
141+66.0	47.0 LT	142+08.0	46 LT												42.0				
142+08.0	46 LT	142+50.0	29.8 LT												45.0				
142+50.0	29.8 RT	145+46.0	31.2 LT												302.2				
136+92.0	70.7 RT	137+15.0	75.5 RT												23.5				
137+15.0	75.5 RT	137+31.0	135.1 RT												61.7				
137+31.0	135.1 RT	138+00.0	95.4 RT												79.6				
138+00.0	95.4 RT	139+33.0	97.3 RT												133.0				
136+98.3	51.6 LT																		
137+81.6	90.8 RT														1				
142+16.2	110.7 RT														1				
134+50.2	24.54 RT														1				
135+03.0	28.26 RT														1				
139+55.7	52.03 LT														1				
140+18.7	51.85 LT														1				
141+68.7	27.94 LT														1				
142+59.6	21.39 LT														1				
143+95.0	21.6 LT														1				
145+26.6	21.4 LT														1				
136+92.7	22.8 RT														1				
137+95.0	RT														10.0				
138+80.0	RT														13.5				
140+63.0	RT														8.0				
141+58.0	RT														8.0				
142+34.0	RT														43.0				
CITY STREET																			
10+74.0	59.0 LT	10+99.0	35.0 LT												34.7				
10+99.0	35.0 LT	12+00.0	35.0 LT												101.0				
12+00.0	35.0 LT	12+53.0	49.7 LT												55.0				
10+81.0	45.7 RT	11+50.0	43.2 RT												69.0				
11+50.0	43.2 RT	12+00.0	50 RT												50.5				
12+00.0	50 RT	12+53.0	46.8 RT												53.1				
11+75.7	44.5 RT														1				
12+55.1	47.0 RT														1				
ACCESS RD																			
20+69.0	86.6 LT	23+00.0	41.0 LT												235.5				
23+00.0	41.0 LT	23+50.0	43.9 LT												50.1				
23+50.0	43.9 LT	23+77.0	67.0 LT												35.5				
23+77.0	67.0 LT	24+19.0	64.3 LT												42.1				
24+19.0	64.3 LT	24+19.0	43.2 LT												21.1				
24+19.0	43.2 LT	24+19.0	67.6 RT												110.8				
24+19.0	67.6 RT	24+07.0	73.7 RT												13.5				
20+97.0	62.2 RT	23+01.0	26.5 RT												207.1				
23+01.0	26.5 RT	23+48.0	37.0 RT												48.2				
23+48.0	37 RT	23+60.0	66.7 RT												32.0				
TOTAL				1.10	5,318.3	3.0	112.5	112.5	112.5	800.2	800.2	250.0	2,282.0	3.0	9.0	2.0	82.5		
ROUNDED				1.25	5,319.0	3.0	113.0	113.0	113.0	801.0	801.0	250.0	2,282.0	3.0	9.0	2.0	83.0		

* MULCH, METHOD 2 USED FOR TEMPORARY AND PERMANENT SEEDING.

FILE NAME = 0876015-shr-schedule2.dgn	USER NAME = dwoznarski	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE. 103	SECTION 27-1-N	COUNTY ST. CLAIR	TOTAL SHEETS 50	SHEET NO. 8
PLOT SCALE = 200.00' / IN.	CHECKED -	REVISED -	REVISED -		SCALE: NA	SHEET NO. 2 OF 4 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
PLOT DATE = 9/14/2010	DATE - 7/9/2010	REVISED -	REVISED -										
CONTRACT NO. 76015													