

SIGN SCHEDULE

STATION	OFFSET	SIGN	L	W	SIGN PANEL, TY 1	WOOD SIGN SUPPORT	TELESCOPING STEEL SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT
			(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(EACH)
135+62.51	RT	R3-H00L	2.00	2.0	4.0		9.0	1.0
139+08.12	RT	R4-7	2.00	2.5	5.0		9.5	1.0
140+71.92	RT	R4-7	2.00	2.5	5.0		9.5	1.0
142+77.80	RT	R3-H00L	2.00	2.0	4.0		9.0	1.0
145+46.68	RT	R3-H00L	2.00	2.0	4.0		9.0	1.0
20+87.69	LT	R6-1	3.00	1.0	3.0	17.0		
		R6-1	3.00	1.0	3.0			
		R1-1	3.00	3.0	9.0			
		R6-3	2.00	1.5	3.0			
		W4-4P	2.00	1.0	2.0			
10+41.10	LT	R6-1	3.00	1.0	3.0	17.0		
		R6-1	3.00	1.0	3.0			
		R1-1	3.00	3.0	9.0			
		R6-3	2.00	1.5	3.0			
		W4-4P	2.00	1.0	2.0			

TOTAL			62.0	34.0	46.0	5.0		
--------------	--	--	------	------	------	-----	--	--

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

STATION	OFFSET	EACH
137+03.85	100.19 LT	1
138+00.14	99.62 LT	1
139+54.91	94.51 LT	1
139+54.77	252.72	1
140+24.77	252.78 LT	1
140+24.92	92.19 LT	1
141+00.15	89.71 LT	1
142+50.17	29.76 LT	1
138+00.21	100.38 RT	1
139+44.91	100.34 RT	1
140+31.92	107.45 RT	1
142+00.22	145.26 RT	1
142+62.36	145.24 RT	1
140+62.83	206.90 RT	1
141+99.28	251.28 RT	1
142+62.48	251.23 RT	1
TOTAL		16

REMOVE SIGN PANEL ASSEMBLY

STATION	OFFSET	TYPE A (EACH)	TYPE B (EACH)
135+61.74	33.10 RT	1	
136+10.41	28.62 RT	1	
140+98.98	26.09 LT	1	
142+04.81	40.31 LT		1
142+52.58	20.24 RT	1	
142.61.30	25.54 RT	1	
142+78.90	29.39 RT	1	
143+35.53	28.47 LT		1
144+54.59	27.51 LT	1	
144+58.22	17.98 RT	1	
TOTAL		8	2

RELOCATE SIGN PANEL ASSEMBLY, TYPE A

FROM		TO		QTY
STATION	OFFSET	STATION	OFFSET	(EACH)
138+89.00	71.5	138+50.00	73.5	1