EX R.O.W.

AC EX ROW AC AC AC

FURNISHING AND ERECTING RIGHT-OF-WAY MARKER

AC EX ROW AC AC AC

FURNISHING AND ERECTING RIGHT-OF-WAY MARKER

CONSTRUCTION LIMITS

PR SUB-BASE GRANULAR MATERIAL, TYPE A, 12"

PR HMA BASE COURSE WIDENING, 12"

PR POLYMERIZED HMA SURFACE COURSE, MIX "D", N70, 2"

PR SUB-BASE GRANULAR MATERIAL, TYPE A, 12"

PR PCC BASE COURSE WIDENING, 12" (CONSTRUCTED MONOLITHICALLY WITH CURB AND GUTTER)

PR POLYMERIZED HMA SURFACE COURSE, MIX "D", N70, 2"

EXIST. CURVE CUR_6
PI STA. = 134+72.86
Δ = 26° 59' 48" (LT)
D = 4° 51' 10"
R = 1,180.66'
T = 283.42'
L = 556.31'
E = 33.54'
e = -----
T.R. = -----
S.E. RUN = -----
P.C. STA. = 131+89.44
P.T. STA. = 137+45.75

N

133 EX ℄ 13/15

134 +85.30 11.8 RT

PR HMA SHOULDER, 10"

BEGIN IMPROVEMENTS STA 133+85.3

TRANSITION FROM B-6.24 C&G TO B-6.12

+03.52 13.5 RT

+04.61 20.4 RT

135+00

CONCRETE MEDIAN, TYPE SB-6.24

+32.43 11.3 RT

CONCRETE MEDIAN SURFACE, 4"

136

EX HMA SHOULDER

PR COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

137

IL ROUTE 13/15

PT Sta 137+45.75

MATCH LINE - STA 138+00

6.5'R

301'R

+61.69 25.5 RT

+85.30 44.5 RT

+94.28 43.2 RT

180' TAPER

300'R

+32.41 27.9 RT

+04.09 26.4 RT

EX HMA

EX PCC

380' LT. TURN LANE

+90.2 59.6 RT

+94.4 60.5 RT

PROPOSED HMA SHOULDERS, 10"

PR COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12

EX HMA SHOULDER

FURNISHING AND ERECTING RIGHT-OF-WAY MARKER

EX R.O.W.

EX ROW

CONSTRUCTION LIMITS

20' 0 20' 40'
SCALE: 1" = 20'

EX ℄ PROFILE

+82 ELEV. 493.72 +0.88%

SPECIAL DITCH RT. PROFILE

+0.56%

+00 ELEV. 488.95

SPECIAL DITCH LT. PROFILE

505 500 495 490 485 480 475

497.25 497.03 496.81 496.64 496.60 496.63 496.91 496.85 496.70 496.80 496.66 496.92

133+00 134+00 135+00 136+00 137+00 138+00

FILE NAME = D876D15-sht-plan1.dgn	USER NAME = dwozniarski	DESIGNED -	REVISED -
		DRAWN - DMW	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 9/14/2010	DATE - 7/9/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 13/15
PLAN AND PROFILE

SCALE: 1"=20' | SHEET NO. 1 OF 5 SHEETS | STA. 133+00 | TO STA. 138+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	27-1-N		50	17
		CONTRACT NO. 76D15		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		