
SCHEDULE OF QUANTITIES								
CODE NO.	ITEM	UNIT	QUANTITY					
80396100	LOCATING UNDERGROUND CABLE	FOOT	12					
88696600	DETECTOR LOOP REPLACEMENT	FOOT	272					



## DETAIL (NO SCALE)

## RE-USE EXISTING DETECTOR LOOP LEAD-IN CONDUIT

- DRILL OUT PAVEMENT SEALANT AND CLEAN EXISTING CONDUIT.

  REMOVE EXISTING CABLE TO HANDHOLE.

  INSTALL LOOP LEAD-IN CONDUCTORS IN CONDUIT.

  SPLICE NEW DETECTOR LOOP LEAD-IN CONDUCTORS TO EXISTING LEAD-IN CABLE IN HANDHOLE.

  FILL HOLE WITH APPROVED SEALER, PREVENT SEALER FROM ENTERING INTO CONDUIT.

NOT A PAY ITEM. THE COST OF THIS WORK SHALL BE INCLUDED IN THE PAY ITEM "DETECTOR LOOP REPLACEMENT"

## TRAFFIC SIGNALS LEGEND

EVPS	EMERGENCY VEHICLE PRIORITY SYSTEM
GSC	GALVANIZED STEEL CONDUIT
PVCC	POLYVINYL CHLORIDE CONDUIT
UD	UNIT-DUCT
0-0	EXISTING SIGNAL POST
O+1>	EXISTING SIGNAL POST WITH BACKPLATE
<b>a</b>	EXISTING TRAFFIC SIGNAL MAST ARM
	EXISTING HANDHOLE
22	EXISTING DOUBLE HANDHOLE
H	EXISTING HEAVEY DUTY HANDHOLE
	EXISTING DETECTOR LOOP
	EXISTING CONTROLLER
<u> </u>	EXISTING STREET NAME SIGN/TRAFFIC SIGN
	EXISTING ILLUMINATED SIGN
<b>-</b> D-	EXISTING SERVICE INSTALLATION
$\bowtie$	EXISTING EMERGENCY VEHICLE SYSTEM DETECTOR (E.V.P.S.)
•	EXISTING (E.V.P.S.) CONFIRMATION BEACON
-0	EXISTING SIGNAL HEAD, PEDESTRIAN
<b></b>	EXISTING PEDESTRIAN PUSHBUTTON DETECTOR
	EXISTING GALVANIZED STEEL CONDUIT
	PROPOSED SIGNAL HEAD WITH BACKPLATE, MAST ARM MOUNTED
₩	PROPOSED EMERGENCY VEHICLE SYSTEM DETECTOR (E.V.P.S.)
•	PROPOSED (E.V.P.S.) CONFIRMATION BEACON
	PROPOSED HANDHOLE
	PROPOSED DOUBLE HANDHOLE
EI	PROPOSED HEAVEY DUTY HANDHOLE
	PROPOSED DETECTOR LOOP
	PROPOSED CONTROLLER
	PROPOSED PEDESTRIAN PUSHBUTTON DETECTOR
-1	PROPOSED SIGNAL HEAD, PEDESTRIAN
•	PROPOSED CONDUIT: "T" TRENCH, "P" PUSH, SIZE SPECIFIED
	PROPOSED STREET NAME SIGN/TRAFFIC SIGN
<b>—</b>	PROPOSED ILLUMINATED SIGN
	PROPOSED SERVICE INSTALLATION
•-	PROPOSED SIGNAL POST
<b>O</b> I <b>&gt;</b>	PROPOSED SIGNAL POST WITH BACKPLATE

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -					F.A.P.	SECTION	COUNTY	TOTAL SHEET
\$FILEL\$		DRAWN -	REVISED -	STATE OF ILLINOIS DETECTOR LOOP DETAILS		Ì	829	103RS	MONROF	16 8	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION			ł			CONTRACT NO. 76098	
	PLOT DATE = \$DATE\$	DATE -	REVISED -		SCALE: NA	SHEET NO. 1 OF 2 SHEETS STA. TO STA	١.	FED. ROAD D	DIST. NO.   ILLINOIS FED.	AID PROJECT	- 100 1000