

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FED 10% STATE 0021 URBAN	-----	-----	CODE NO	ITEM	UNIT		-----	-----	-----
44000400	GUTTER REMOVAL	FOOT	1958	1958									
44004250	PAVED SHOULDER REMOVAL	SO YD	3877	3877									
48101200	AGGREGATE SHOULDERS, TYPE B	TON	213	213									
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	3877	3877									
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	10	10									
60602500	CONCRETE GUTTER, TYPE A	FOOT	1511	1511									
64200105	SHOULDER RUMBLE STRIPS	FOOT	7521	7521									
67100100	MOBILIZATION	L SUM	1	1									
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1									
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1									
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1171	1171									
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	12884	12884									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	390	390									
78300100	PAVEMENT MARKING REMOVAL	SO FT	4295	4295									
X0325866	CENTER LINE - RUMBLE STRIP	FOOT	6442	6442									
*X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	19884	19884									
*SPECIALTY ITEM													