

# SUMMARY OF QUANTITIES

			CONSTRUCTION TYPE CODE						CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED 20% STATE URBAN 0005		CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED 20% STATE URBAN 0005	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18.2	18.2		*78200520	BARRIER WALL MARKERS, TYPE B	EACH	68	68	
40600300	AGGREGATE (PRIME COAT)	TON	88	88		*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	266	266	
40600990	TEMPORARY RAMP	SQ YD	112	112		X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	2431	2431	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4874	4874		Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	6	6	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	94185	94185		● Z0076600	<b>TRAINEES</b>	<b>HOUR</b>	<b>500</b>	<b>500</b>	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	50	50							
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	40	40							
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	80	80							
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	458	458							
48203100	HOT-MIX ASPHALT SHOULDERS	TON	4532	4532							
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	500	500							
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2							
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2							
63200310	GUARDRAIL REMOVAL	FOOT	500	500							
63800024	GLARE SCREEN BLADES 24"	EACH	475	475							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6							
67100100	MOBILIZATION	L SUM	1	1							
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1							
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1							
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1							
70300100	SHORT TERM PAVEMENT MARKING	FOOT	10680	10680							
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	208	208							
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	47660	47660							
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	48	48							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	15485	15485							
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	208	208							
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	47660	47660							
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	48	48							
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	266	266							
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8							

\*SPECIALTY ITEM

● 0042

FILE NAME *	USER NAME * #USER#	DESIGNED -	REVISED -
#FILE#		DRAWN -	REVISED -
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -
	PLOT DATE = #DATE#	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	(31-2, 30-2)RS-2	JEFFERSON	7	3
CONTRACT NO. 76E36				
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

SCALE: NONE    SHEET NO. 1 OF 1 SHEETS    STA.    TO STA.