

RESURFACING SCHEDULE						
STATION		BITUMINOUS				
		AGGREGATE	MATERIALS	POLY-LEVEL	HMA	HMA SURFACE
SOUTHBOUND		(PRIME COAT)	(PRIME COAT)	BINDER	SURFACE CSE.	REMOVAL, 1 1/2"
		TON	TON	TON	TON	SQ YD
575+00.00	TO 612+00.00	14.80	3.09	414.4	828.8	17111.1
612+00.00	TO 618+00.00	3.00	0.63	84.0	168.0	3066.7
618+00.00	TO 644+00.00	10.40	2.17	291.2	582.4	11555.6
644+00.00	TO 649+00.00	2.50	0.53	70.0	140.0	2555.6
649+00.00	TO 680+91.00	12.77	2.67	357.4	714.8	14182.2
NORTHBOUND						
575+00.00	TO 608+00.00	13.20	2.76	369.6	739.2	13933.3
608+00.00	TO 613+00.00	2.50	0.53	70.0	140.0	2555.6
613+00.00	TO 640+00.00	10.80	2.26	302.4	604.8	11400.0
640+00.00	TO 645+00.00	2.50	0.53	70.0	140.0	2555.6
645+00.00	TO 680+91.00	14.37	3.00	402.2	804.4	15162.0
SIDE ROADS		0.30	0.06		11.2	106
TOTAL		88	18.2	2,431	4874	94,185

SHOULDER SCHEDULE				
STATION		AGGREGATE	HOT-MIX	
		WEDGE	ASPHALT	
SOUTHBOUND		SHOULDERS	SHOULDERS, 1"	
		TON	TON	
575+00.00	TO 577+00.00	4.98	44.8	
577+00.00	TO 607+90.00	38.45	756	
607+90.00	TO 680+91.00	181.71	1655.6	
NORTHBOUND				
575+00.00	TO 577+80.00	6.97	54.9	
577+80.00	TO 602+90.00	31.24	492	
602+90.00	TO 680+91.00	194.16	1529	
TOTAL		458	4,532	

TEMPORARY RAMP SCHEDULE				
LOCATION		WIDTH	LENGTH	TEMPORARY
				RAMP
SOUTHBOUND		FOOT	FOOT	SQ YD
STA	575+00.00	24	5	14
STA	612+62.00	24	5	14
STA	644+27.00	24	5	14
STA	680+91.00	24	5	14
NORTHBOUND				
STA	575+00.00	24	5	14
STA	612+62.00	24	5	14
STA	644+27.00	24	5	14
STA	680+91.00	24	5	14
TOTAL				112

GUARDRAIL SCHEDULE							
	STEEL PLATE	TRAFFIC BARRIER					
	BEAM GUARDRAIL	TERMINAL, TYPE 1	STEEL PLATE	TRAFFIC BARRIER	TERMINAL MARKER	GUARDRAIL MARKER,	BARRIER WALL
	REMOVAL	(SPECIAL) TANGENT	BEAM GUARDRAIL	TERMINAL, TYPE 6	DIRECT APPLIED	TYPE A	MARKERS, TYPE B
	FOOT	EACH	FOOT	EACH	EACH	EACH	EACH
NORTH END OF SB BARRIER	400	1	400	1	1	6	38
SOUTH END OF NB BARRIER	100	1	100	1	1	2	30
TOTAL	500	2	500	2	2	8	68

GLARE SCREEN BLADES	
	GLARE SCREEN
	BLADES 24"
	EACH
SOUTHBOUND	341
NORTHBOUND	54
20% anticipated failure	80
TOTAL	475

PAVEMENT MARKING SCHEDULE															
STATION		THERMOPLASTIC PAVEMENT MARKING							TEMPORARY PAVEMENT MARKING					WORK ZONE	
		EDGE LINE	EDGE LINE	CENTERLINE	LETTERS &	STOP BAR	RAISED REFLECTIVE	RAISED REFLECTIVE	SHORT TERM	EDGE LINE	EDGE LINE	SKIP-DASH	LETTERS &	STOP BAR	PAVEMENT
		4" WHITE	4" YELLOW	4" WHITE	SYMBOLS	12" WHITE	REMOVAL	PAVEMENT MARKER	PAVEMENT MARKER	MARKING	4" WHITE	4" YELLOW	4" WHITE	SYMBOLS	12" WHITE
SOUTHBOUND		FOOT	FOOT	FOOT	SQ FT	FOOT	EACH	EACH	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	SQ FT
STA.	575+00.00 TO 612+00.00	3700.0	3700.0	92.5			46	46	1865.0	3700.00	3700.00	92.50			2704.7
STA.	612+00.00 TO 618+00.00	600.0	600.0	15.0	52.0	12.0	8	8	305.0	600.00	600.00	15.00	52.0	12.0	438.9
STA.	618+00.00 TO 644+00.00	2600.0	2600.0	65.0			33	33	1312.0	2600.00	2600.00	65.00			1900.8
STA.	644+00.00 TO 649+00.00	500.0	500.0	12.5	52.0	12.0	6	6	254.0	500.00	500.00	12.50	52.0	12.0	365.7
STA.	649+00.00 TO 680+91.00	3191.0	3191.0	79.8			40	40	1609.0	3191.00	3191.00	79.78			2332.7
NORTHBOUND															
STA.	575+00.00 TO 608+00.00	3300.0	3300.0	82.5			42	42	1662.0	3300.00	3300.00	82.50			2412.2
STA.	608+00.00 TO 613+00.00	500.0	500.0	12.5	52.0	12.0	6	6	252.0	500.00	500.00	12.50	52.0	12.0	365.5
STA.	613+00.00 TO 640+00.00	2700.0	2700.0	67.5			34	34	1360.0	2700.00	2700.00	67.50			1973.6
STA.	640+00.00 TO 645+00.00	500.0	500.0	12.5	52.0	12.0	6	6	252.0	500.00	500.00	12.50	52.0	12.0	365.5
STA.	645+00.00 TO 680+91.00	3591.0	3591.0	89.8			45	45	1809.0	3591.00	3591.00	89.78			2624.9
SUB-TOTAL		21182.0	21182.0	529.6	208.0	48.0	266	266	10680	21182.00	21182.00	529.55	208.0	48.0	15484.52
TOTAL		21182	21182	530	208	48	266	266	10680	21182	21182	530	208	48	15485
GRAND TOTAL		42,894		208	48	266	266	10,680	42,894		208	48	15,485		