

GENERAL NOTES

1. THE STANDARDS AND REVISIONS LISTED APPLY TO THIS PROJECT.
2. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT INTERCHANGES, ENTRANCES AND SIDE STREETS WHERE WORK IS BEING CONDUCTED AS DIRECTED BY THE RESIDENT ENGINEER. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE. THIS SHALL BE INCLUDED IN THE COST OF THE TRAFFIC CONTROL AND PROTECTION. THESE SIGNS SHALL BE 48" X 48".
3. ALL TURF AREAS DISTURBED BY THE CONTRACTOR SHALL BE SEEDED INCLUDING EROSION CONTROL AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.
4. IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16, THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 107.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
5. NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED.
6. THE FOLLOWING PAIRS OF STRUCTURES SHALL BE STAGED AS ONE WORK ZONE AND WORK PERFORMED CONCURRENTLY ON EACH PAIR:

SN 060-0276 AND SN 060-0278
 SN 060-0277 AND SN 060-0279
 SN 060-0280 AND SN 060-0313
 SN 060-0281 AND SN 060-0314

COMMITMENTS

THERE ARE NO COMMITMENTS.

BRIDGE LOCATIONS

STRUCTURE NO.	ROUTE	OVER	LOCATION	NET LENGTH	TRAFFIC DATA			
					ADT 2011	ADT 2031	% SU	% MU
SN 060-0272	IL 255 NB	COUNTY DITCH	1.25 MILES NORTH OF I-270	212.00	15200	18500	4.0	6.0
SN 060-0273	IL 255 SB	COUNTY DITCH	1.25 MILES NORTH OF I-270	212.00	15000	18300	4.8	6.1
SN 060-0274	IL 255 NB	OLD POAG ROAD & NORFOLK SOUTHERN RAILROAD	2.5 MILES NORTH OF I-270	329.59	14200	17300	3.6	4.3
SN 060-0275	IL 255 SB	OLD POAG ROAD & NORFOLK SOUTHERN RAILROAD	2.5 MILES NORTH OF I-270	327.65	13800	16800	4.1	4.4
SN 060-0276	IL 255 NB	NEW POAG ROAD	2.7 MILES NORTH OF I-270	221.41	11900	14500	5.7	4.9
SN 060-0277	IL 255 SB	NEW POAG ROAD	2.7 MILES NORTH OF I-270	221.40	12500	15300	5.7	4.9
SN 060-0278	IL 255 NB	CAHOKIA DIVERSION	SOUTH CORPORATE LIMITS OF ROXANA	427.50	11900	14500	5.7	4.9
SN 060-0279	IL 255 SB	CAHOKIA DIVERSION	SOUTH CORPORATE LIMITS OF ROXANA	427.50	11900	14500	5.7	4.9
SN 060-0280	IL 255 NB	UPRR	4 MILES NORTH OF I-270	333.44	11900	14500	5.7	4.9
SN 060-0281	IL 255 SB	UPRR	4 MILES NORTH OF I-270	334.91	12500	15300	5.7	4.9
SN 060-0282	IL 255 NB	WAGON WHEEL ROAD	3.75 MILES NORTH OF I-270	118.22	11900	14500	5.7	4.9
SN 060-0283	IL 255 SB	WAGON WHEEL ROAD	3.75 MILES NORTH OF I-270	118.78	11900	14500	5.7	4.9
SN 060-0284	IL 255 NB	FAU 8975	0.25 EAST OF SOUTH ROXANA	205.00	11100	13500	3.7	4.1
SN 060-0285	IL 255 SB	FAU 8975	0.25 EAST OF SOUTH ROXANA	205.00	11300	13800	5.4	4.5
SN 060-0286	IL 255 NB	IL 143	IN ROXANA	254.99	11100	13500	3.7	4.1
SN 060-0287	IL 255 SB	IL 143	IN ROXANA	235.15	11300	13800	5.4	4.5
SN 060-0289	IL 255 NB	IL 111	NORTH OF IL 143	214.89	9400	11500	4.3	3.8
SN 060-0290	IL 255 SB	IL 111	NORTH OF IL 143	225.26	9100	11100	5.3	3.9
SN 060-0291	AIRLINE DRIVE	IL 255	0.95 MILES SOUTHWEST OF IL 140	241.14	9000	11100	2.3	0.4
SN 060-0294	IL 255	IL 140	IN BETHALTO	158.62	16100	19600	4.9	4.3
SN 060-0295	IL 255 NB	EAST FORK WOOD RIVER CREEK	0.75 MILE SOUTH OF CULP	292.99	5500	6700	2.3	1.1
SN 060-0296	IL 255 SB	EAST FORK WOOD RIVER CREEK	0.75 MILE SOUTH OF CULP	289.19	5200	6300	4.4	1.2
SN 060-0313	IL 255 NB	FARMERS ACCESS ROAD	2 MILES SOUTH OF IL 143	87.79	11900	14500	5.7	4.9
SN 060-0314	IL 255 SB	FARMERS ACCESS ROAD	2 MILES SOUTH OF IL 143	88.21	12500	15300	5.7	4.9
TOTAL =				5782.63				

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION



GENERAL NOTES

SCALE: NONE

SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	DIST 8 BRIDGE DECK 2011-2	MADISON	29	2
CONTRACT NO. 76E42				
ILLINOIS FED. AID PROJECT				

LAST SAVED = 9/9/2010
 USER = jpepittbone
 PLOT DRIVER = TR-20066204-TopFile.plt

FILE NAME =	USER NAME = jpepittbone	DESIGNED -	REVISED -
1:\0906600\0906604\cad\t\location\plan	1\02_0876E42-Sht-GenNote.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0023 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 11/30/2010 2:12:49 PM	DATE -	REVISED -