

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	Existing Length (Inform. Only) FOOT	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A. 6 FT. POSTS FOOT	TRAFFIC BARRIER TERMINAL				TERMINAL MARKERS - DA EACH	GUARDRAIL MARKERS - TA EACH	CONC. SUPER-STRUC. CU YD	RE INF. BARS (EPOX. CT.) POUNDS	BRIDGE HANDRAIL REMOVAL FOOT
				TY 1, SPL (TAN) EACH	TYPE 2 EACH	TYPE 6 EACH	TYPE 10 EACH					
EASTBOUND FAI 64												
097-0001 WEST OUTSIDE APPROACH												
RT 5824+93.00												
RT 5824+93.00 TO RT 5827+88.96	296	296						1				
RT 5825+33.00 TO RT 5827+46.00			212.5						4			
RT 5827+88.96						1				0.27	55.4	9.0
097-0001 WEST MEDIAN APPROACH												
LT 5824+54.00												
LT 5826+69.00 TO LT 5827+88.96	120	120						1				
LT 5825+03.96 TO LT 5827+45.21			250.0						4			
LT 5827+88.96						1				0.27	55.4	9.0
097-0001 EAST OUTSIDE DEPARTURE												
RT 5830+83.04												
RT 5830+83.04 TO RT 5849+76.79	1894	1894										
RT 5830+83.04 TO RT 5849+64.29			1887.5						26			
RT 5849+76.79								1				
097-0003 WEST OUTSIDE APPROACH												
RT 5871+01.00												
RT 5871+01.00 TO RT 5875+27.05	426	426							1			
RT 5871+51.00 TO RT 5874+83.30			337.5						4			
RT 5875+27.05										0.27	55.4	9.0
097-0003 WEST MEDIAN APPROACH												
LT 5871+01.00												
LT 5871+01.00 TO LT 5875+27.05	426	426							1			
LT 5871+51.00 TO LT 5874+83.30			337.5						4			
LT 5875+27.05										0.27	55.4	9.0
SUBTOTALS FAI 64 EASTBOUND		3162	3025	4	1	4	1	5	42	1.06	221.6	36.0
WESTBOUND FAI 64												
097-0002 WEST OUTSIDE DEPARTURE												
LT 5824+57.00												
LT 5824+57.71 TO LT 5827+88.96	331	331							1			
LT 5824+70.00 TO LT 5827+88.96			325.0						4			
LT 5827+88.96								1				
097-0002 EAST OUTSIDE APPROACH												
LT 5830+83.04												
LT 5830+83.04 TO LT 5850+26.79	1944	1944								0.27	55.4	9.0
LT 5831+14.00 TO LT 5849+76.79			1862.5						24			
LT 5850+26.79								1				
097-0002 EAST MEDIAN APPROACH												
RT 5830+83.04												
RT 5830+83.04 TO RT 5832+26.79	144	144								0.27	55.4	9.0
RT 5831+27.00 TO RT 5833+81.00			262.5						4			
RT 5834+31.00								1				
097-0004 WEST OUTSIDE DEPARTURE												
LT 5872+40.00												
LT 5873+62.00 TO LT 5875+27.05	165	165							1			
LT 5872+52.05 TO LT 5875+27.05			275.0						4			
LT 5875+27.05								1				
097-0004 WEST MEDIAN DEPARTURE												
RT 5868+39.55												
RT 5868+52.00 TO RT 5875+27.05	675	675										
RT 5868+52.50 TO RT 5875+27.05			675.0						9			
RT 5875+27.05								1				
SUBTOTALS FAI 64 WESTBOUND		3259	3400	2	3	2	3	5	45	0.53	110.8	18.0
PROJECT TOTALS:		6420.62	6421	6425	6.0	4.0	6.0	4.0	10.0	1.59	332.4	54.0