

**PAVEMENT MARKING SCHEDULE**  
**FAI 64 WESTBOUND LANES AND RAMPS**

LOCATION STATION TO STATION	LENGTH ( INFORMATION ONLY)	PREFORMED PLASTIC LINE 6"	PREFORMED PLASTIC LINE 4"		PREF. PLASTIC LINE 8" (ON RAMP GOES)	SHORT-TERM PAVEMENT MARKING		TEMP PAVT MRK - LINE 6"	TEMP PAVT MRK - LINE 4"	TEMP PAVT MRK - LINE 8"	NOTES
		WHITE (SKIP-DASH) FEET	SOLID WHITE (LT EOP) FEET	SOLID YELLOW (RT EOP) FEET	SOLID WHITE FEET	MAINLINE SKIP-DASH FEET	SHOULDER SKIP-DASH FEET	MAINLINE SKIP-DASH FEET	SHOULDER STRIPE FEET	GORE STRIPE FEET	
<b>FAI 64 (I-64) WESTBOUND</b>											
<b>MAINLINE</b>											
	5800+32.00 TO 5827+88.96	2757.0	690		2757		440	690	2757		M. L. & RT. SHLD.
LT	5809+75.00 TO 5811+00.00	125.0			125					125	ALONG GORE
LT	5811+00.00 TO 5820+87.00	987.0	987				40		987		
LT	5820+87.00 TO 5825+27.00	440.0			440					440	ALONG GORE
<b>OMIT STR. NO. 097-0002</b>											
	5830+83.00 TO 5875+27.00	4444.0	1110		4444		712	1110	4444		M. L. & RT. SHLD.
LT	5830+83.00 TO 5847+23.00	1640.0		1640			68		1640		
LT	5856+92.00 TO 5859+35.00	243.0			243					243	
LT	5859+35.00 TO 5867+88.00	853.0		853			36		853		
LT	5867+88.00 TO 5871+63.00	375.0			375					375	
LT	5874+65.00 TO 5875+27.05	62.1		62					62		
<b>RAMP A</b>											
RT	70+40.00 TO 100+32.14	2992		2992			120		2992		SEE NOTE BELOW
LT	70+40.00 TO 89+56.00	1916		1916					1916		SEE NOTE BELOW
LT	89+56.00 TO 90+81.00	125			125					125	
LT	90+81.00 TO 94+00.00	319	80					80			
<b>RAMP B</b>											
RT	227+88.0 TO 251+89.0	2401		2401			96		2401		SEE NOTE BELOW
LT	230+50.0 TO 234+90.0	440			440					440	
LT	234+90.0 TO 251+89.0	1699		1699					1699		SEE NOTE BELOW
<b>ENTRANCE RAMP TO FAI 64 FROM REST AREA</b>											
LT	5847+23.0 TO 5856+93.0	970		970			40		970		SEE NOTE BELOW
LT	0 TO 343	343		343			14		343		SEE NOTE BELOW
RT	0 TO 230	230			230					230	
LT	5854+92.41 TO 5856+92.39	200	50					50			
RT	230 TO 343	113		113					113		
<b>EXIT RAMP FROM FAI 64 TO REST AREA</b>											
LT	5867+88.00 TO 5874+65.00	677		677			28		677		SEE NOTE BELOW
LT	5867+88.00 TO 5871+63.00	375			375					375	
<b>SUBTOTALS</b>			1930	10925	10929	2353	1152	442	1930	21854	2353
<b>WESTBOUND TOTALS</b>			1930	21854	2353	1594		1930	21854	2353	
<b>PROJECT TOTALS</b>			3830	43665	3388	3185		3830	43665	3388	

NOTE: FOR THE RAMPS, THE SOLID WHITE LINE IS ON THE RIGHT EDGE OF PAVEMENT AND THE SOLID YELLOW LINE IS ON THE LEFT EDGE OF PAVEMENT.