



PREF. PLASTIC PAVEMENT MARKING  
 TYPE B - INLAID - LINE 4"  
 (WHITE) - 951 FT.  
 RT. STA. 90+80.90 TO RT. STA. 100+32.14

PREF. PLASTIC PAVEMENT MARKING  
 TYPE B - INLAID - 4"  
 (YELLOW) - 2757 FT.  
 RT. STA. 5800+32 TO RT. STA. 5827+89

FAI 64 WEST BOUND LANES  
 FAI 64 MEDIAN  
 FAI 64 EAST BOUND LANES

PREF. PLASTIC PAVEMENT MARKING  
 TYPE B - INLAID - LINE 4"  
 (WHITE) - 2694 FT.  
 RT. STA. 401+21 TO  
 RT. STA. 428+15

PREF. PLASTIC PAVEMENT MARKING  
 TYPE B - INLAID - 8"  
 (WHITE) - 380 FT.  
 RT. STA. 5804+26.39 TO RT. STA. 5808+05.52

PREF. PLASTIC PAVEMENT MARKING  
 TYPE B - INLAID - 8"  
 (WHITE) - 380 FT.  
 LT. STA. 404+20 TO LT. STA. 408+00

PROP. PROJECT BEGINS  
 STA 5800+32.00 ( BUTT JT )  
 SAW CUT FOR HMA SURFACE REMOVAL -  
 BUTT JOINT

PREF. PLASTIC PAVEMENT MARKING  
 TYPE B - INLAID - 4"  
 (YELLOW) - 2757 FT.  
 LT. STA. 5800+32 TO LT. STA. 5827+89

PREF. PLASTIC PAVEMENT MARKING  
 TYPE B - INLAID - 4"  
 (WHITE) - 88 FT.  
 RT. STA. 5800+32 TO RT. STA. 5801+20

NOTE: ALL STATIONING FOR PAY ITEM LOCATIONS ARE BASED  
 ON THE CENTERLINE OF THE LANES THEY ARE RELATED.

FILE NAME =	USER NAME = mcoordkr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>FAI 64 PAVEMENT MARKING</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
at:\pw\work\p\idot\mcoordkr\08186975\sh	plan.dgn	DRAWN -	REVISED -			64	197-21RS-2	WHITE	34	17	
PLOT SCALE = 100,0000' / IN.	CHECKED -	REVISED -	REVISED -			<b>CONTRACT NO. 78211</b>					
PLOT DATE = 11/3/2010	DATE -	REVISED -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. OF SHEETS STA. TO STA.					