

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 0014		JEFFERSON CO.			
		RURAL			
		100% STATE			
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	IL 37 041-0032	IL 57 041-0055
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7		7
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	18		18
42001300	PROTECTIVE COAT	SQ YD	1417	1372	45
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	164		164
50102400	CONCRETE REMOVAL	CU YD	33.2	23.4	9.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	33.6	22.8	10.8
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6150	4920	1230
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4980	3560	1420
52000110	PREFORMED JOINT STRIP SEAL	FOOT	242	176	66
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24	24	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	24	12	12
52100520	ANCHOR BOLTS, 1"	EACH	96	72	24
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	112	112	
63302700	REMOVE AND RE ERECT TRAFFIC BARRIER TERMINALS, TYPE 6	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	1	1
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1		1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	0.5	0.5
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	1	1
X5017305	PROTECTIVE SHIELD (PERMANENT)	SQ YD	93		93
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	48	36	12
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	22.6		22.6
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	7	7	
Z0049790	RELOCATING NAME PLATES	EACH	2	1	1

*SPECIALTY ITEM

FILE NAME = g:\pwork\pwork\goutneyr\0819879\78212-ah-tr-plen.dgn

USER NAME = goutneyrk	DESIGNED - ---	REVISED - ---
PLOT SCALE = 25:0:0 1" / IN.	DRAWN - ---	REVISED - ---
PLOT DATE = 12/22/2010	CHECKED - ---	REVISED - ---
	DATE - ---	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	D9 CM BRIDGE REPAIR 2011-2	JEFFERSON	24	3
*F.A.S. 2869 & F.A.I. 57		CONTRACT NO. 78233		
ILLINOIS FED. AID PROJECT				