

AGGREGATE SHOULDERS, TYPE B 4"		
STATION	SQ YD	REMARKS
SCOUT CAMP ROAD		
L 10+50.00 TO 11+96.05	65	
L 11+96.05 TO 13+18.37	133	
L 14+69.29 TO 22+32.76	345	
L 22+67.92 TO 24+50.00	82	
R 10+50.00 TO 11+48.26	42	
R 11+48.26 TO 13+18.37	123	
R 14+01.63 TO 15+33.08	107	
R 15+33.08 TO 24+50.00	396	
SUBTOTAL:	1,293	
WELCH ROAD		
R 81+99.52 TO 83+40.66	120	
SUBTOTAL:	120	
PROJECT TOTAL	1,413	

PIPE CULVERTS, CLASS A, TYPE 1 24"		
STATION	FOOT	REMARKS
SCOUT CAMP ROAD		
L & R 22+80.00	45	ACROSS ROAD
PROJECT TOTAL	45	

PIPE CULVERTS, CLASS A, TYPE 2 30"		
STATION	FOOT	REMARKS
WELCH ROAD		
83+00.00	55	ACROSS ROAD
PROJECT TOTAL	55	

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"		
STATION	EACH	REMARKS
SCOUT CAMP ROAD		
L & R 22+80.00	2	
PROJECT TOTAL	2	

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"		
STATION	EACH	REMARKS
WELCH ROAD		
L & R 83+00.00	2	
PROJECT TOTAL	2	

TRAFFIC BARRIER TERMINAL, TYPE 6A		
STATION	EACH	REMARKS
SCOUT CAMP ROAD		
R 12+72.46 TO 13+19.47	1	
L 12+78.37 TO 13+22.28	1	
L 13+97.72 TO 14+29.15 L 42.44'	1	AT WELCH ROAD RADIUS
R 14+00.53 TO 14+47.54	1	
PROJECT TOTAL	4	

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		
STATION	EACH	REMARKS
SCOUT CAMP ROAD		
R 12+20.92 TO 12+72.46	1	
R 14+47.54 TO 14+99.08	1	
L 12+30.05 TO 12+78.37	1	
SUBTOTAL:	3	
WELCH ROAD		
R 82+57.52 TO 83+07.72	1	
SUBTOTAL:	1	
PROJECT TOTAL	4	

BARBED WIRE FENCE, FIVE STRAND		
STATION	FOOT	REMARKS
SCOUT CAMP ROAD		
LT 10+23.64 TO 13+86.48	386	ALONG PROP. ROW
LT 14+81.05 TO 21+96.03	813	ALONG PROP. ROW
LT 22+91.14 TO 24+50	215	ALONG PROP. ROW
RT 10+50 TO 24+50	1,361	ALONG PROP. ROW
WELCH ROAD		
LT 80+28.77 TO 82+81.82	261	ALONG PROP. ROW
82+00 TO 83+03.28	108	ALONG PROP. ROW
PROJECT TOTAL	3,144	

PERMANENT SURVEY MARKERS, TYPE II		
STATION	EACH	REMARKS
SCOUT CAMP ROAD		
R 14+52.15	1	FUTURE LOCATION TO BE DETERMINED
PROJECT TOTAL	1	

PAINT PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
SCOUT CAMP ROAD		
L 10+50.00 TO 14+00.80	356	EDGE LINE (WHITE)
L 14+85.66 TO 24+50.00	984	EDGE LINE (WHITE)
R 10+50.00 TO 24+50.00	1,375	EDGE LINE (WHITE)
10+50.00 TO 24+50.00	2,800	DBL @ CL (YELLOW)
SUBTOTAL:	5,515	
WELCH ROAD		
L 80+50.00 TO 83+39.00	312	EDGE LINE (WHITE) - INCL RADIUS
R 80+50.00 TO 83+90.00	306	EDGE LINE (WHITE) - INCL RADIUS
80+50.00 TO 82+90.00	480	DBL @ CL (YELLOW)
SUBTOTAL:	1,098	
PROJECT TOTAL	6,613	

PAINT PAVEMENT MARKING - LINE 24"		
STATION	FOOT	REMARKS
SCOUT CAMP ROAD		
R 82+90.00	9	STOP BAR (WHITE)
PROJECT TOTAL	9	

FILE = S:\PROJECTS\1169009\JoDaviesCo_ScoutCampRoad\DESIGN\STRUCT\COVERETC.dgn

REV.	DATE	BY	REMARKS

DRAWN	X.X.X.
CHECKED	X.X.X.
APPROVED	X.X.X.

**JO DAVIESS COUNTY
SCOUT CAMP ROAD AND
WELCH ROAD IMPROVEMENTS**

F.A.S. 73
FED. AID PROJECT -
FED. ROAD DIST. NO. 7 ILLINOIS

SCHEDULES OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
09-00133-00-BR	JO DAVIESS	48	9
STA.	STA.		
WHA PROJECT: 1169009		DATE: XX/XX/XXXX	