

RESURFACING SCHEDULE (Continued)		LENGTH	AVERAGE PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX 7/8", N90	LEVELING BINDER (MACHINE METHOD), N90	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
STATION	TO STATION														
		FOOT	FOOT	SQ FT	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	TON	TON	SQ YD	SQ YD
RAMP C															
0+13.50	TO 0+52.50	39.0	VARIABLE	1864.0	207.1	0.0	0.0	41.4	0.4	17.4	8.7	0.0	2.0	0.0	0.0
0+52.50	TO 22+61.00	2208.5	28.0	61838.0	6870.9	0.0	0.0	1374.2	13.7	577.2	288.6	0.0	115.3	0.0	0.0
22+61.00	TO 28+61.00	600.0	VARIABLE	22022.0	2446.9	0.0	0.0	489.4	4.9	205.5	102.8	0.0	31.3	0.0	0.0
28+61.00	TO 29+95.00	134.0	28.0	3752.0	416.9	0.0	0.0	83.4	0.8	35.0	17.5	0.0	7.0	0.0	0.0
29+95.00	TO 30+30.00	35.0	28.0	980.0	0.0	0.0	108.9	21.8	0.2	9.1	4.6	0.0	1.8	0.0	0.0
30+30.00	TO 36+50.00	620.0	28.0	17360.0	0.0	0.0	1928.9	385.8	3.9	162.0	81.0	0.0	0.0	0.0	46.7
RAMP E															
0+00.00	TO 13+46.37	1346.4	24.0	32312.9	3590.3	0.0	0.0	718.0	7.2	301.6	150.8	0.0	70.3	0.0	0.0
RAMP A															
1+00.00	TO 1+35.00	35.0	20.0	700.0	0.0	0.0	0.0	15.6	0.2	6.5	1.6	0.0	3.1	77.8	11.1
1+35.00	TO 9+37.00	802.0	20.0	16040.0	1782.2	0.0	0.0	356.4	3.6	149.7	74.9	0.0	69.8	0.0	0.0
9+37.00	TO 9+72.00	35.0	20.0	700.0	0.0	0.0	0.0	15.6	0.2	6.5	1.6	0.0	3.1	77.8	11.1
RAMP B															
1+00.00	TO 1+35.00	35.0	22.0	770.0	0.0	0.0	0.0	17.2	0.2	7.2	1.8	0.0	3.1	85.6	12.2
1+35.00	TO 5+88.52	453.5	22.0	9977.4	1108.6	0.0	0.0	221.8	2.2	93.1	46.6	0.0	39.5	0.0	0.0
5+88.52	BK= 6+25.19 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
6+25.19	TO 9+20.00	294.8	22.0	6485.8	720.6	0.0	0.0	144.2	1.4	60.5	30.3	0.0	25.6	0.0	0.0
9+20.00	TO 9+55.00	35.0	22.0	770.0	0.0	0.0	0.0	17.2	0.2	7.2	1.8	0.0	3.1	85.6	12.2
RAMP TOTALS				175572.0	17144.0	0.0	2038.0	3902.0	39.0	1639.0	813.0	0.0	375.0	327.0	93.0
TOTALS				1659861.0	179701.0	1663.0	2038.0	36887.0	369.0	15492.0	7655.0	391.0	4437.0	1027.0	336.0