

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2122-B	COOK	75	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PROJECT LOCATION: FAI 57 (DAN RYAN EXPRESSWAY) AT 103RD STREET
SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN			
			TOTAL QUANTITY <i>100% FED.</i>	ROADWAY 1000-2A	BRIDGE X271-2A	LIGHTING Y030-1E
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	20	20		
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	20	20		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	504	504		
50102400	CONCRETE REMOVAL	CU YD	68		68	
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1	
50157300	PROTECTIVE SHIELD	SQ YD	936		936	
50200100	STRUCTURE EXCAVATION	CU YD	44		44	
50300225	CONCRETE STRUCTURES	CU YD	64		64	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	588		588	
50300260	BRIDGE DECK GROOVING	SQ YD	1,225		1,225	
50300300	PROTECTIVE COAT	SQ YD	1,754		1,754	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6,980		6,980	
50500505	STUD SHEAR CONNECTORS	EACH	5,400		5,400	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	120,300		120,300	
50800515	BAR SPLICERS	EACH	811		811	
50901730	BRIDGE FENCE RAILING	FOOT	532		532	
51205200	TEMPORARY SHEET PILING	SQ FT	232		232	
51500100	NAME PLATES	EACH	2		2	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	135		135	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24		24	
52100520	ANCHOR BOLTS, 1"	EACH	48		48	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	81	81		
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	295	295		
56109210	WATER VALVES TO BE ADJUSTED	EACH	1	1		
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1		
58700300	CONCRETE SEALER	SQ FT	1020		1020	
59000200	EPOXY CRACK INJECTION	FOOT	137		137	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	7	7		
60255500	MANHOLES TO BE ADJUSTED	EACH	14	14		
60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	306	306		
66400105	CHAIN LINK FENCE, 4'	FOOT	40	40		
66410300	CHAIN LINK FENCE REMOVAL	FOOT	40	40		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTICN, (SPECIAL)	L SUM	1	1		

• SPECIALTY ITEM

NP= NON-PARTICIPATING



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 2 OF 4

SCALE: NONE
 DATE: 1/15/2009

DRAWN BY: R.T.T.
 CHECKED BY: A.A.C.

1/15/2009 06:03:59ql.dgn