

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2122-B	COOK	75	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**PROJECT LOCATION: FAI 57 (DAN RYAN EXPRESSWAY) AT 103RD STREET**  
**SUMMARY OF QUANTITIES**

CODE NUMBER	ITEM	UNIT	URBAN			
			TOTAL QUANTITY <i>100% FED.</i>	ROADWAY I000-2A	BRIDGE X271-2A	LIGHTING Y030-1E
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	210	210		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,878	2,878		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	508	508		
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	109	109		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	9592	9592		
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	836	836		
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	675	675		
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	81	81		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	434	434		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	604	604		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	220	220		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	30	30		
* 73303000	OVERHEAD SIGN STRUCTURE - SPAN, MONOTUBE	FOOT	67	67		
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109	109		
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	4,179	4,179		
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	836	836		
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	545	545		
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	81	81		
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	26	26		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	108	108		
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	40			40
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	50			50
* 81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	65			65
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	240			240
? * 81100705	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., GALVANIZED STEEL (PVC COATED)	FOOT	156			156
? * 81100905	CONDUIT ATTACHED TO STRUCTURE, 3 1/2" DIA., GALVANIZED STEEL (PVC COATED)	FOOT	2554			2554
? * 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	395			395
? * 81200250	CONDUIT EMBEDDED IN STRUCTURE, 3" DIA., PVC	FOOT	20			20
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	8			8
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	4			4
* 81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	4			4
* 81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	296			296
* 81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	1,472			1,472

SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
**SHEET 3 OF 4**  
 SCALE: NONE  
 DATE: 1/15/2009  
 DRAWN BY: R.T.T.  
 CHECKED BY: A.A.C.



1/15/2009 06-103csq01.dgn