

**PROJECT LOCATION: FAI 57 (DAN RYAN EXPRESSWAY) AT 103RD STREET**

**SUMMARY OF QUANTITIES**

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2122-B	COOK	75	6a
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	ITEM	UNIT	URBAN		
			TOTAL QUANTITY <i>100% FED.</i>	ROADWAY 1000-2A	BRIDGE X271-2A
*B1700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 6	FOOT	184		184
*B1700125	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 4	FOOT	552		552
*B1800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	300		300
*B1900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	440		440
*B4200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	8		8
*B4200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	12		12
*B4200700	LIGHTING FOUNDATION REMOVAL	EACH	4		4
*B7900100	DRILL EXISTING FOUNDATION	EACH	4		4
*B7900200	DRILL EXISTING HANDHOLE	EACH	4		4
*E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	60	60	
X0301766	DRILL AND GROUT #6 TIE BARS	EACH	154	154	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	64	64	
*X0322453	WEED CONTROL, PRE-EMERGENT	POUND	30	30	
*X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6		6
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4		4
X0323859	DOWNSPOUT CONNECTION	EACH	4	4	
*X0324198	REMOVAL OF ASBESTOS CEMENT CONDUIT	FOOT	1,500	1,500	
*X0324302	REMOVAL OF TEMPORARY LIGHTING FIXTURE, SALVAGE	EACH	12		12
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	98		98
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	894		894
*X0329867	INSTALL LIGHT POLE MAST ARM & LUMINAIRE (MATERIAL PROVIDED BY THE CITY OF CHICAGO)	EACH	8		8
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1	
MP X0005656	INLET FILTER CLEANING	EACH	8	8	
Z0011400	COLD MILLING EXISTING MEDIAN	SQ YD	102	102	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0017202	DOWEL BARS 1 1/2"	EACH	32	32	
MP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4	
Z0018800	DRAINAGE SYSTEM	L SUM	1		1
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2	2	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1	
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
Z0031301	JACKING AND CRIBBING, LOCATION NO. 1	L SUM	1		1
Z0031302	JACKING AND CRIBBING, LOCATION NO. 2	L SUM	1		1
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	3		3
*X0326323	UNDERPASS LUMINAIRE, 70WATT, <sup>HIGH PRESSURE SODIUM</sup> VAPOR, STAINLESS STEEL HOUSING	EACH	20		20
*X0326328	<sup>LIGHTING</sup> STREET CABLE, 1/C NO. 6, CITY OF CHICAGO STANDARD	FOOT	1104		1104
*X0326329	<sup>LIGHTING</sup> STREET CABLE, 1/C NO. 8, CITY OF CHICAGO STANDARD	FOOT	552		552
*A2005036	TREE, GYMNOCLADUS DIOICUS EXPRESSO (EXPRESSO KENTUCKY COFFEETREE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	7	7	
⊙ Z0076600	TRAINERS	HR	1000	1000	

SPECIALTY ITEM

Y080

MP- NON-PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
**SHEET 4 OF 4**

SCALE: NONE  
DATE: 1/15/2009

DRAWN BY: R.T.T.  
CHECKED BY: A.A.C.



1/15/2009 06:10:30seq01.dgn