

Pavement Marking Tape, Type III - Line 12" (Ft)

Stage I	Begin STA	End STA	Type	Length
	-0+72.26	3+56.80	Median Diag.	130

Prior to Permanent Markings				
Begin STA	End STA	Type	Length	
-0+72.26 RT	3+58.30 RT	Shldr Diag.	335	
7+04.70 RT	9+69.50 RT	Median Diag.	145	
8+12.90 LT	10+17.80 LT	Shldr Diag.	65	

TOTAL = 675 FT

Temporary Concrete Barrier (Ft)

Station 4+12.03 to Station 6+75.49

Length = 220 ft

Shoulder of I-57

Length = 340 ft

TOTAL = 604 FT

Pavement Marking Tape, Type III - L & S (Sq Ft)

Epoxy Pavement Markings - L/S (Sq Ft)

Description	Area (sq ft)	Quantity	Total Area (sq ft)
Direction Arrow	15.20	3.00	45.60
ONLY	21.10	3.00	63.30

TOTAL = 109 SQ FT

Epoxy Pavement Marking - Line 4" (Ft)

Begin STA	End STA	Type	Length (ft)
-0+72.26	3+58.30	Dbl Yellow	861.12
	2+54.80 LT	White	9.0
2+54.80 LT	3+58.30 LT	White	103.5
	-0+72.26 RT	White	12.0
-0+72.26 RT	3+58.30 RT	White	430.56
4+38.10	6+35.10	Dbl Yellow	394
	7+04.70	Dbl Yellow	25
7+04.70 RT	9+69.50 RT	Dbl Yellow	529.6
7+04.70 LT	9+69.50 LT	Dbl Yellow	529.6
6+96.50	12+28.85	Dbl Yellow	1064.7
8+12.90 LT	10+17.80 LT	White	204.9
	10+17.80 LT	White	15

TOTAL = 4,179 FT

Pavement Marking Tape, Type III - Line 6" (Ft)

Epoxy Pavement Marking - Line 6" (Ft)

Intersection	Location	Length	
103rd/Elizabeth	North	75	Crosswalk
103rd/Elizabeth	West	100	Crosswalk
103rd/Elizabeth	South	70	Crosswalk
103rd/Racine	North	85	Crosswalk
103rd/Racine	East	100	Crosswalk
103rd/Racine	South	85	Crosswalk
4+38.10	6+35.10	197	Turn Lane Line (LT)
4+38.10	5+35.10	24	Skip Dash
5+35.10	6+35.10	100	Turn Lane Line (RT)

TOTAL = 836 FT

Epoxy Pavement Marking - Line 12" (Ft)

Begin STA	End STA	Type	Length
-0+72.26 RT	3+58.30 RT	Shldr Diag.	335
7+04.70 RT	9+69.50 RT	Median Diag.	145
8+12.90 LT	10+17.80 LT	Shldr Diag.	65

TOTAL = 545 FT

Pavement Marking Tape, Type III - Line 24" (Ft)

Epoxy Pavement Marking - Line 24" (Ft)

Location	Length
Elizabeth St. South of 103rd St	15
Elizabeth St. North of 103rd St	31
Racine Ave. South of 103rd St	35

TOTAL = 81 FT

Pavement Marking Removal (Sf)

Location	Item	Length
103rd St West of Bridge	4" skip dash	34.67
103rd St East of Bridge	4" skip dash	39.82
Bridge	4" skip dash (2)	33.33

TOTAL = 108 SQ FT

COLD MILLING EXISTING MEDIAN (SQ YD)

Length (Ft)	Width (Ft)	Area
230	4	920 SQ FT
		102 SQ YD

TOTAL = 102 SQ YD

DOWNSPOUT CONNECTION, EACH

LOCATION
103rd St STA 5+26.12, 22.55 LT
103rd St STA 6+26.86, 22.55 LT
103rd St STA 5+26.12, 23.70 RT
103rd St STA 6+26.86, 23.70 RT

TOTAL = 4 EACH

15-JAN-2009 S:\111\09a-103\aschedq03.dgn



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SHEET 3 OF 3

SCALE: NONE
 DATE: 15-JAN-2009

DRAWN BY: D.K.J.
 CHECKED BY: A.A.C.