


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	ZIP CODE	SHEET NO.	SHEET NO. 1 2 SHEETS
F.A.I. 57	★	COOK	75 27		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT			

Contract 60366
★ 2122B



GENERAL NOTES

DESIGN: Current (at time of letting) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals.

CONSTRUCTION: Current (at time of letting) Illinois Department of Transportation Standard Specifications for Road and Bridge Construction, Supplemental Specifications and Recurring Special Provisions. ("Standard Specifications") All references to "Mast Arm Assembly and Pole" are applicable, unless otherwise noted.

WELDING: All welds to be continuous unless otherwise shown. All welding to be done in accordance with current AWS D1.1 Structural Welding Code and the Standard Specifications.

ANCHOR RODS: Shall meet Charpy V-notch (CVN) energy of 15 lb-ft at 40° F. No welding shall be permitted on rods.

FASTENERS: All connection bolts shall be High Strength Bolts M164, Galvanize M232 (A153), Type 3, or stainless steel heavy hex conforming to ASTM A193, Grade B8 or B8M, Class 1. U-bolts shall be produced from ASTM A276 Type 304, 304L, 316 or 316L, Condition A, cold finished, or an equivalent material acceptable to the Engineer. Nuts for stainless steel bolts shall be stainless steel conforming to ASTM A194, Grade 8 (AISI Type 304) or Grade 8F (AISI Type 303). All nuts shall be "locknuts" with nylon or steel inserts and semifinished hexagonal heads equivalent to the finished heavy hex series of the American National Standard. Washers for stainless steel bolts shall be stainless steel conforming to ASTM A240, Type 302 or 304.

REINFORCEMENT BARS: Reinforcement Bars designated (E) shall be epoxy coated in accordance with the Standard Specifications.

CAMBER: Minimum AASHTO camber = $L / 1000$ + dead load camber.

FOUNDATIONS: See Structure Plans for foundation support and payment of anchor rods.

SIGN STRUCTURE DATA TABLE

Structure Number	Station	ϕ to ϕ Poles	Elevation A	Dimension D	Actual Sign/Signal Area	Left Foundation					Right Foundation					Class SI Concrete (Cu. Yds.)
						Elevation Top	Elev. Bottom	A	B	F	Elevation Top	Elev. Bottom	A	B	F	
IM016L000R000.0	5+47.40	67'-2"	617.00	8'-7"	30 sf	619.75	---	---	---	---	619.75	---	---	---	---	---

NUMBER	REVISION	DATE

BILL OF MATERIAL

ITEM	UNIT	TOTAL
OVERHEAD SIGN STRUCTURE SPAN, MONOTUBE	Foot	67

DESIGNED	NDR
CHECKED	DSE
DRAWN	RTT
CHECKED	DSE
DATE	JAN 16, 2009

Illinois Firm Registration No. 184-00633



Stanley Consultants Inc.
850 West Higgins Road, Suite 730, Chicago, Illinois 60631-2801
www.stanleygroup.com

MONOTUBE SIGN STRUCTURE
103RD STREET OVER
FAI 57 (DAN RYAN-WEST LEG)
FAI RTE 57 SECTION 2122B
COOK COUNTY
STA 5+47.40