

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	1919.2B	COOK	119	5
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT 60371

SUMMARY OF QUANTITIES		100% FED. URBAN		CONSTRUCTION TYPE CODES			
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000	BRIDGE X731-2A	TRAFFIC SIGNAL-Y031-1F	HIGHWAY LIGHTING Y030-1E
M2520110	SODDING, SALT TOLERANT	SO M	132	132			
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	4	4			
M2800400	PERIMETER EROSION BARRIER	METER	338	338			
M3111100	SUB-BASE GRANULAR MATERIAL, TYPE B 100MM	SO M	12	12			
M3530230	PORTLAND CEMENT CONCRETE BASE COURSE 230MM	SO M	12	12			
M4030200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	1.7	1.7			
M4060300	AGGREGATE (PRIME COAT)	M TON	11	11			
M4060400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	M TON	1.2	1.2			
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO M	98	98			
M4060990	TEMPORARY RAMP	SO M	164	164			
M4061005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	M TON	21	21			
M4062135	LEVELING BINDER (MACHINE METHOD), N70	M TON	215	215			
M4063085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	M TON	223	223			
M4063340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	328	328			
M4200260	PORTLAND CEMENT CONCRETE PAVEMENT 260MM	SO M	103	103			
M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SO M	366	366			
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SO M	108	108			
M4240125	PORTLAND CEMENT CONCRETE SIDEWALK 125MM	SO M	659	659			
M4245000	TEMPORARY SIDEWALK	SO M	109	109			
M4248000	DETECTABLE WARNINGS	SO M	43	43			
M4400760	HOT-MIX ASPHALT SURFACE REMOVAL, 60MM	SO M	3272	3272			
M4401160	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 60MM	SO M	232	232			
M4402000	PAVEMENT REMOVAL	SO M	285	285			
M4402010	DRIVEWAY PAVEMENT REMOVAL	SO M	108	108			
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	416	416			
M4402050	SIDEWALK REMOVAL	SO M	500	500			
M4402060	APPROACH SLAB REMOVAL	SO M	234	234			
M4427020	CLASS C PATCHES, TYPE I, 225MM	SO M	85	85			
M4427220	CLASS C PATCHES, TYPE II, 225MM	SO M	69	69			
M4427320	CLASS C PATCHES, TYPE III, 225MM	SO M	78	78			
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	795	795			
M5010240	CONCRETE REMOVAL	CU M	30.3		30.3		
M5010570	PROTECTIVE SHIELD	SO M	1475		1475		
M5020100	STRUCTURE EXCAVATION	CU M	136		136		
M5030350	CONCRETE STRUCTURES	CU M	24.8		24.8		
M5030360	CONCRETE SUPERSTRUCTURE	CU M	477.7		477.7		
M5030390	BRIDGE DECK GROOVING	SO M	1087		1087		
M5030450	PROTECTIVE COAT	SO M	2218	641	1577		
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	6520		6520		

== SPECIALTY ITEM
 += NON PARTICIPATING ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 DRAWN BY: PRH
 CHECKED BY: JMH
 DATE: JANUARY 16, 2009

COLLINS ENGINEERS
 123 North Wacker Drive
 Suite 300
 Chicago, IL 60606
 (312) 704-9300
 www.collinsengr.com
 ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184-000993

FILE: g:\2904\civil\exhibit\2904005.dgn
 DATE: 19-Nov-07 15:52