

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODES			
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	100% FED. URBAN			
				ROADWAY 1000	BRIDGE X731-2A	TRAFFIC SIGNAL-Y031-1F	HIGHWAY LIGHTING Y030-1E
M8170435	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 2-1/C NO. 2	METER	80			80	
M8170470	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 4	METER	56				56
M8170820	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C NO. 2/0	METER	157				157
M8180120	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	METER	215				215
M8180240	AERIAL CABLE, 4-1/C NO. 8 WITH MESSENGER WIRE	METER	135				135
M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	140				140
M8190302	TRENCH AND BACKFILL WITH SCREENINGS OR SAND	METER	123				123
M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	8.4			4.2	4.2
M8360200	LIGHT POLE FOUNDATION, 750MM DIAMETER	METER	19.5			19.5	
M8731185	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 19C	METER	307			307	
M8780500	CONCRETE FOUNDATION (SPECIAL)	METER	3			3	
M8950230	REMOVE ELECTRIC CABLE FROM CONDUIT	METER	800			800	
MX030208	CONDUIT ATTACHED TO STRUCTURE, 65MM DIA. GALVANIZED STEEL, PVC COATED	METER	54				54
MX030300	CONDUIT ATTACHED TO STRUCTURE, 25MM DIA. GALVANIZED STEEL, PVC COATED	METER	132				132
MX032016	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SPECIAL	SO M	73	73			
MX032178	TEMPORARY INFORMATION SIGNING	SO M	14	14			
MX032198	MAST ARM, STEEL, MONOTUBE 12.19 METER	EACH	3			3	
MX032309	ELECTRIC MANHOLE, 900MM X 1.2M X 1.2M, WITH 600MM FRAME AND LID	EACH	1				1
MX032313	MAST ARM, STEEL, MONOTUBE 10.70 METER	EACH	2			2	
MX032322	ADJUST <sup>JNG</sup> EXISTING ELECTRICAL MANHOLE WITH 600MM FRAME AND LID	EACH	6			6	
MX032324	MAST ARM, STEEL, MONOTUBE 9.10 METER	EACH	1			1	
MX032634	PVC CONDUIT IN TRENCH 3-75MM (SCHEDULE #80)	METER	25.0			10.0	15.0
MX032680	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	KG	14	14			
MX032750	MAST ARM, STEEL, STREET LIGHTING, 3.66 METER	EACH	2				2
MX032760	ELECTRICAL HANDHOLE, 760MM DIAMETER WITH 600MM FRAME AND LID	EACH	2				2
MX032767	CONCRETE FOUNDATION, 500MM DIAMETER	METER	1.5				1.5
MX032985	VIDEO TAPING STORM SEWERS	METER	698	698			
MX033100	REMOVAL OF ASBESTOS CEMENT CONDUIT	METER	228		228		
MX033364	TRENCH AND BACKFILL FOR 2 TO 4 DUCTS	METER	82			33	49
M8100280	CONDUIT IN TRENCH, 75MM DIA., PVC	METER	17.5				17.5
MX033367	PVC CONDUIT IN TRENCH 2-75MM (SCHEDULE #80)	METER	10			10	
M8120230	CONDUIT EMBEDDED IN STRUCTURE, 50MM DIA., PVC	METER	160				160
M8100260	CONDUIT IN TRENCH, 50MM DIA., PVC	METER	160				160
MX033694	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 125MM)	SO M	43		43		
MX703200	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III	METER	3457	3457			
<del>MX810060</del>	<del>CONDUIT IN TRENCH, 50MM DIA., PVC, SCHEDULE #80</del>	<del>METER</del>	<del>5</del>				<del>5</del>
MX830101	LIGHT POLE, STEEL, 10.5M M.H., 3.65M MAST ARM, 7 GAUGE 254MM DIA., 381MM BOLT CIRCLE, 31.75MM ANCHOR RODS	EACH	2			2	
MX830104	LIGHT POLE, STEEL, 10.5M M.H., 3.65M MAST ARM, 3 GAUGE 318MM DIA., 419MM BOLT CIRCLE, 38.1MM ANCHOR RODS	EACH	5			5	
MX870010	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 2/C NO. 6 AND NO. 8 GROUND	METER	627				627

== SPECIALTY ITEM  
 += NON PARTICIPATING ITEM

FILE: g:\2904\civil\exhibit\2904007.dgn  
 DATE: 19-Nov-07 15:59

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SUMMARY OF QUANTITIES

DRAWN BY: PRH  
 CHECKED BY: JMH

DATE: JANUARY 16, 2009

**COLLINS ENGINEERS**  
 123 North Waukegan Drive  
 Suite 300  
 Chicago, IL 60606  
 (312) 704-9300  
 www.collinsengr.com  
 ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184-000993