

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODES			
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	100% FED. URBAN			
				ROADWAY 1000	BRIDGE X731-2A	TRAFFIC SIGNAL-Y031-IF	HIGHWAY LIGHTING Y030-1E
MZ037300	PAVEMENT GROOVING	SQ M	103	103			
X0320564	SOLID STATE PRETIMED CONTROLLER, 40 CIRCUIT, 24 INTERVAL, WITH ACTUATION INPUTS WITH FOUR CYCLE SOLID STATE TIME BASE COORDINATOR IN BASE INTO CABINET	EACH	2			2	
X0322424	TEMPORARY UNDERPASS LIGHTING INSTALLATION AND REMOVAL	L SUM	1				1
X0322425	CIRCUIT BREAKER, 1-POLE, 70 AMPERE, 480 VOLT IN EXISTING STREET LIGHT CONTROLLER	EACH	2			2	
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	9				9
X0324571	MAINTENANCE OF STREET LIGHTING SYSTEM (CITY OF CHICAGO)	L SUM	1				1
X0324893	BREAKDOWN HANDHOLE OR MANHOLE	EACH	3			1	2
X0329863	INTERCEPT EXISTING CONDUIT	EACH	3			2	1
X0329867	INSTALL LIGHT POLE MAST ARM & LUMINAIRE (MATERIAL PROVIDED BY THE CITY OF CHICAGO)	EACH	6				6
X0329888	REMOVE EXISTING STREET LIGHTING EQUIPMENT	L SUM	1				1
X0966500	SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, MAST ARM MOUNTED	EACH	4			4	
X0966600	SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, BRACKET MOUNTED	EACH	4			4	
X0966705	JUNCTION BOX, POLE OR POST MOUNTED, SPECIAL	EACH	8			8	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4	4			
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1			
X6040220	FRAMES AND LIDS, TYPE 1, OPEN LID (CITY OF CHICAGO)	EACH	1	1			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
X8040100	ELECTRIC CONNECTION TO SIGN STRUCTURE	EACH	2				2
X8210451	LUMINAIRE, STREET LIGHTING, HIGH PRESSURE SODIUM VAPOR, 400 WATT, 240 VOLT	EACH	11				11
X8950090	RELOCATE EXISTING LIGHTING CONTROLLER	EACH	1				1
XX002293	REMOVE, STORE, AND RE-ERECT OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	2		2		
XX005656	INLET FILTER CLEANING	EACH	16	16			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5		
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	19	19			
Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	1			1	
Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	4	4			
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	EACH	2	2			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
Z0076600	TRAINEES	HOUR	1000	1000			
MX033763	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 10C	METER	140			140	
MX033765	LIGHT POLE, STEEL, 10.5M M.H., 3.65M MAST ARM, 3 GAUGE 279MM DIA., 438MM BOLT CIRCLE, 31.75MM ANCHOR RODS	EACH	1			1	
X8210454	LUMINAIRE, STREET LIGHTING, HIGH PRESSURE SODIUM VAPOR, 195 WATT, 240 VOLT	EACH	2				2
MX033766	MAST ARM, STEEL, STREET LIGHTING, 2.40 METER	EACH	3				3
MX033767	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SO M	11	11			
MX033764	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	METER	440			440	
MX033468	STORM SEWER, DUCTILE IRON PIPE, TYPE 2, 200MM	METER	36	36			
A2005036	TREE, GYMNOCLADUS DIOICUS EXPRESSO (EXPRESSO KENTUCKY COFFEETREE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	11	11			

\*\* SPECIALTY ITEM  
 += NON PARTICIPATING ITEM  
 © Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWN BY: PRH  
 CHECKED BY: JMH  
 DATE: JANUARY 16, 2009



FILE: G:\2904\civil\exhibit\2904008.dgn  
 DATE: 19-NOV-07 15:59