

PROJECT: I-90 (KENNEDY EXPRESSWAY) AT CENTRAL AVENUE  
COOK COUNTY

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	1213B-1	COOK	94	4
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 60640				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY 100% FED.	ROADWAY	BRIDGE	ROADWAY LIGHTING	TRAFFIC SURVEILLANCE
				1000-2A	X831-2A	1000-2A	1000-2A
20101100	TREE TRUNK PROTECTION	EACH	3	3			
28000510	INLET FILTERS	EACH	4	4			
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1		
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	30		30		
50800515	BAR SPLICERS	EACH	970		970		
51500100	NAME PLATES	EACH	1		1		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	30		30		
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3			
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	4	4			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
67100100	MOBILIZATION	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	50			
70106800	CHANGEABLE MESSAGE SIGN	CAL MQ	2	2			
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	1	1			
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	70	70			
80500300	SERVICE INSTALLATION, TYPE C	EACH	1				1
* 81400200	HEAVY-DUTY HANDHOLE	EACH	5				5
* <del>X0326323</del>	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	8			8	
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	8			8	
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	2			2	
* 87900200	DRILL EXISTING HANDHOLE	EACH	17			17	
* 89500510	CABINET HOUSING EQUIPMENT REMOVAL	EACH	2				2
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1				1
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2				2
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	20	20			
M2011000	TEMPORARY FENCE	METER	300	300			
M2020010	EARTH EXCAVATION	CU M	271	271			
M2070400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU M	107		107		
M2113100	TOPSOIL FURNISH AND PLACE, 100MM	SQ M	148	148			

\* SPECIALTY ITEM

**CR & A**  
CHRISTIAN-ROGE & ASSOCIATES, INC.  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: JANUARY 16, 2009

DRAWN BY: A.C.S.  
CHECKED BY: S.J.P.