

PROJECT: I-90 (KENNEDY EXPRESSWAY) AT CENTRAL AVENUE  
COOK COUNTY

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	1213B-1	COOK	94	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 60640

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY 100% FED.	ROADWAY	BRIDGE	ROADWAY LIGHTING	TRAFFIC SURVEILLANCE
				I000-2A	X831-2A	I000-2A	I000-2A
M2500210	SEEDING, CLASS 2A	HA	0.03	0.03			
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	1	1			
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	1	1			
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	1	1			
M2510630	EROSION CONTROL BLANKET	SQ M	300	300			
M2520110	SODDING, SALT TOLERANT	SQ M	148	148			
M2520200	SUPPLEMENTAL WATERING	UNIT	1	1			
M2800400	PERIMETER EROSION BARRIER	METER	45	45			
M3111100	SUB-BASE GRANULAR MATERIAL, TYPE B 100MM	SQ M	299	299			
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	1	1			
M4060300	AGGREGATE (PRIME COAT)	M TON	10	10			
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	25	25			
M4061005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	M TON	66	66			
M4062135	LEVELING BINDER (MACHINE METHOD), N70	M TON	100	100			
M4063340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	150	150			
M4202265	PORTLAND CEMENT CONCRETE PAVEMENT 260MM (JOINTED)	SQ M	414	414			
M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ M	346	346			
M4206100	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ M	24	24			
M4230250	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 250 MM	SQ M	37	37			
M4240125	PORTLAND CEMENT CONCRETE SIDEWALK 125MM	SQ M	224	224			
M4248000	DETECTABLE WARNINGS	SQ M	5	5			
M4400765	HOT-MIX ASPHALT SURFACE REMOVAL, 65MM	SQ M	1,523	1,523			
M4401150	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 50MM	SQ M	550	550			
M4402000	PAVEMENT REMOVAL	SQ M	650	650			
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	44	44			
M4402020	CURB REMOVAL	METER	11	11			
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	229	229			
M4402050	SIDEWALK REMOVAL	SQ M	288	288			
M4402060	APPROACH SLAB REMOVAL	SQ M	165	165			
M4402420	MEDIAN REMOVAL	SQ M	140	140			

\* SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: JANUARY 16, 2009

DRAWN BY: A.C.S.  
CHECKED BY: S.J.P.