

PROJECT: I-90 (KENNEDY EXPRESSWAY) AT CENTRAL AVENUE
COOK COUNTY

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	1213B-1	COOK	94	6
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 60640				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY 100% FED.	ROADWAY	BRIDGE	ROADWAY LIGHTING	TRAFFIC SURVEILLANCE
				I000-2A	X831-2A	I000-2A	I000-2A
M4427235	CLASS C PATCHES, TYPE II, 300MM	SQ M	100	100			
M4427335	CLASS C PATCHES, TYPE III, 300MM	SQ M	150	150			
M4427435	CLASS C PATCHES, TYPE IV, 300MM	SQ M	300	300			
M5010240	CONCRETE REMOVAL	CU M	34.5		34.5		
M5010570	PROTECTIVE SHIELD	SQ M	1,206		1,206		
M5020100	STRUCTURE EXCAVATION	CU M	155		155		
M5030350	CONCRETE STRUCTURES	CU M	24.6		24.6		
M5030360	CONCRETE SUPERSTRUCTURE	CU M	491		491		
M5030390	BRIDGE DECK GROOVING	SQ M	1,004		1,004		
M5030450	PROTECTIVE COAT	SQ M	2,400	705	1,695		
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	1,109		1,109		
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	60,850		60,850		
M5090520	BRIDGE FENCE RAILING	METER	168		168		
M5120900	TEMPORARY SHEET PILING	SQ M	25		25		
M5200225	PREFORMED JOINT STRIP SEAL	METER	75		75		
M5210022	ANCHOR BOLTS, M24	EACH	20		20		
** M5504800	STORM SEWERS TO BE CLEANED	METER	77	77			
M5870300	CONCRETE SEALER	SQ M	69		69		
M5900200	EPOXY CRACK INJECTION	METER	36		36		
M6020230	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE I FRAME, OPEN LID (CITY OF CHICAGO)	EACH	1	1			
M6060070	CONCRETE CURB, TYPE B	METER	11	11			
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	171	171			
M6060520	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30 (SPECIAL)	METER	48	48			
M6063753	CONCRETE MEDIAN, TYPE M-5.30 (SPECIAL)	SQ M	14	14			
M6064100	CONCRETE MEDIAN, TYPE SB-15.30	SQ M	47	47			
M6064130	CONCRETE MEDIAN, TYPE SB-15.30 (SPECIAL)	SQ M	114	114			
M6641930	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	METER	42	42			
M7030100	SHORT-TERM PAVEMENT MARKING	METER	25	25			
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	524	524			
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	52	52			

* SPECIALTY ITEM
** NON-PARTICIPATING



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: JANUARY 16, 2009
DRAWN BY: A.C.S.
CHECKED BY: S.J.P.