

PROJECT: I-90 (KENNEDY EXPRESSWAY) AT CENTRAL AVENUE  
COOK COUNTY

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	I213B-1	COOK	94	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 60640				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY 100% FED.	ROADWAY	BRIDGE	ROADWAY LIGHTING	TRAFFIC SURVEILLANCE
				I000-2A	X831-2A	I000-2A	I000-2A
* M8160400	UNIT DUCT, WITH 3-1/C NO.4 AND 1/C NO.6 GROUND, 600V (EPR-TYPE RHW), 30MM DIA., POLYETHYLENE	METER	81			81	
* M8170425	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO.10	METER	403			403	
* M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	893			558	335
* M8780200	CONCRETE FOUNDATION, TYPE D	METER	2				2
* M8950230	REMOVE ELECTRIC CABLE FROM CONDUIT	METER	450			450	
MX030199	TEMPORARY PAVEMENT	SQ M	40	40			
* MX030207	CONDUIT ATTACHED TO STRUCTURE, 50MM DIA. GALVANIZED STEEL, PVC COATED	METER	213				213
* MX030243	CONDUIT ATTACHED TO STRUCTURE, 75MM DIA. GALVANIZED STEEL, PVC COATED	METER	379			379	
* MX030300	CONDUIT ATTACHED TO STRUCTURE, 25MM DIA. GALVANIZED STEEL, PVC COATED	METER	98			98	
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	5	5			
* MX032308	ELECTRIC CABLE IN CONDUIT, 600V (EPRN TRIPLEXED) 2-1/C NO.6, 1-1 C NO.8 GROUND	METER	453			453	
* MX032507	PVC CONDUIT IN TRENCH 50MM (SCHEDULE #80)	METER	71			71	
* MX032768	CONCRETE FOUNDATION, 600MM DIAMETER	METER	10			10	
* MX032777	ELECTRICAL CABLE IN CONDUIT NO.19 6/C	METER	359				359
MX032779	EXTRA STRENGTH CLAY PIPE STORM SEWERS, TYPE 2, 200MM	METER	2	2			
* MX033100	REMOVAL OF ASBESTOS CEMENT CONDUIT	METER	320			320	
MX033693	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 125MM)	SQ M	5.0		5.0		
MX033694	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 125MM)	SQ M	73.7		73.7		
* MX870010	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 2/C NO. 6 AND NO. 8 GROUND	METER	382				382
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	538	538			
** X0320080	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	METER	95			95	
* X0322426	RELOCATE CTA ELECTRICAL SERVICE	L SUM	1	1			
* X0322440	DIGITAL LOOP DETECTOR SENSOR UNIT (2 CHANNEL)	EACH	1				1
* X0322443	TONE EQUIPMENT - 3 FREQUENCY TRANSMITTER PROGRAMMABLE	EACH	2				2
* X0322444	TONE EQUIPMENT - POWER SUPPLY	EACH	1				1
* X0322445	TONE EQUIPMENT - MOUNTING FRAME	EACH	1				1
* X0322446	CABINET HOUSING EQUIPMENT, TYPE III	EACH	2				2
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6			6	
** X0324435	CLEANING EXISTING MANHOLE OR HANDHOLE	EACH	6			6	
X0325015	ADJUST FRAME AND LID	EACH	4			4	

\* SPECIALTY ITEM  
\*\* NON-PARTICIPATING

**CR & A** CHRISTIAN-ROGE & ASSOCIATES, INC.  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
1-312-372-2023 FAX: 1-312-372-5274

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: JANUARY 16, 2009

DRAWN BY: A.C.S.  
CHECKED BY: S.J.P.