F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	1213B-1	COOK	94	54
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 60640

BEAM 4

LOCATION	STATION	OFFSET	THEORET. GRADE EL.	THEORET. GRADE EL. ADJ. FOR DEAD LOAD DEFLECTIONS AND GRINDING
BK. OF S. ABUT.	0+954.621	-2.795	188.218	188.224
CL. BRG. S. ABUT.	0+955.654	-2.795	188.209	188.215
A	0+958.654	-2.795	188.184	188.198
B	0+961.654	-2.795	188.160	188.178
C	0+964.654	-2.795	188.135	188.155
D	0+967.654	-2.795	188.110	188.125
CL. S. BRG. PIER 2	0+971.448	-2.795	188.078	188.084
CL. PIER 2	0+971.637	-2.795	188.077	188.083
CL. N. BRG. PIER 2	0+971.826	-2.795	188.075	188.081
E	0+974.826	-2.795	188.050	188.074
F	0+977.826	-2.795	188.026	188.061
G	0+980.826	-2.795	188.001	188.046
H	0+983.826	-2.795	187.976	188.025
I	0+986.826	-2.795	187.951	187.999
J	0+989.826	-2.795	187.926	187.969
K	0+992.826	-2.795	187.901	187.935
L	0+995.826	-2.795	187.876	187.901
M	0+998.826	-2.795	187.852	187.868
CL. PIER 1	1+003.150	-2.795	187.816	187.822
N	1+006.150	-2.795	187.791	187.797
O	1+009.150	-2.795	187.766	187.775
P	1+012.150	-2.795	187.741	187.758
Q	1+015.150	-2.795	187.716	187.740
R	1+018.150	-2.795	187.691	187.720
S	1+021.150	-2.795	187.666	187.697
T	1+024.150	-2.795	187.637	187.666
U	1+027.150	-2.795	187.602	187.626
V	1+030.150	-2.795	187.562	187.576
CL. BRG. N. ABUT.	1+032.257	-2.795	187.530	187.536
BK. OF N. ABUT.	1+033.290	-2.795	187.514	187.520

BEAM 5

LOCATION	STATION	OFFSET	THEORET. GRADE EL.	THEORET. GRADE EL. ADJ. FOR DEAD LOAD DEFLECTIONS AND GRINDING
BK. OF S. ABUT.	0+953.010	-0.610	188.275	188.281
CL. BRG. S. ABUT.	0+954.043	-0.610	188.266	188.272
A	0+957.043	-0.610	188.241	188.255
B	0+960.043	-0.610	188.217	188.235
C	0+963.043	-0.610	188.192	188.212
D	0+966.043	-0.610	188.167	188.182
CL. S. BRG. PIER 2	0+969.837	-0.610	188.135	188.141
CL. PIER 2	0+970.026	-0.610	188.134	188.140
CL. N. BRG. PIER 2	0+970.215	-0.610	188.132	188.138
E	0+973.215	-0.610	188.107	188.131
F	0+976.215	-0.610	188.083	188.118
G	0+979.215	-0.610	188.058	188.103
H	0+982.215	-0.610	188.033	188.082
I	0+985.215	-0.610	188.008	188.056
J	0+988.215	-0.610	187.983	188.026
K	0+991.215	-0.610	187.958	187.992
L	0+994.215	-0.610	187.933	187.958
M	0+997.215	-0.610	187.909	187.925
CL. PIER 1	1+001.539	-0.610	187.873	187.879
N	1+004.539	-0.610	187.848	187.854
O	1+007.539	-0.610	187.823	187.832
P	1+010.539	-0.610	187.798	187.815
Q	1+013.539	-0.610	187.773	187.797
R	1+016.539	-0.610	187.748	187.777
S	1+019.539	-0.610	187.724	187.754
T	1+022.539	-0.610	187.697	187.726
U	1+025.539	-0.610	187.665	187.689
V	1+028.539	-0.610	187.628	187.642
CL. BRG. N. ABUT.	1+030.646	-0.610	187.598	187.604
BK. OF N. ABUT.	1+031.679	-0.610	187.583	187.589

℄ CENTRAL AVE.

LOCATION	STATION	OFFSET	THEORET. GRADE EL.	THEORET. GRADE EL. ADJ. FOR DEAD LOAD DEFLECTIONS AND GRINDING
BK. OF S. ABUT.	0+952.560	0.000	188.291	188.297
CL. BRG. S. ABUT.	0+953.593	0.000	188.282	188.288
A	0+956.593	0.000	188.257	188.271
B	0+959.593	0.000	188.233	188.251
C	0+962.593	0.000	188.208	188.228
D	0+965.593	0.000	188.183	188.198
CL. S. BRG. PIER 2	0+969.387	0.000	188.151	188.157
CL. PIER 2	0+969.576	0.000	188.150	188.156
CL. N. BRG. PIER 2	0+969.765	0.000	188.148	188.154
E	0+972.765	0.000	188.123	188.147
F	0+975.765	0.000	188.099	188.134
G	0+978.765	0.000	188.074	188.119
H	0+981.765	0.000	188.049	188.098
I	0+984.765	0.000	188.024	188.072
J	0+987.765	0.000	187.999	188.042
K	0+990.765	0.000	187.974	188.008
L	0+993.765	0.000	187.949	187.974
M	0+996.765	0.000	187.925	187.941
CL. PIER 1	1+001.089	0.000	187.889	187.895
N	1+004.089	0.000	187.864	187.870
O	1+007.089	0.000	187.839	187.848
P	1+010.089	0.000	187.814	187.831
Q	1+013.089	0.000	187.789	187.813
R	1+016.089	0.000	187.764	187.793
S	1+019.089	0.000	187.740	187.770
T	1+022.089	0.000	187.713	187.743
U	1+025.089	0.000	187.682	187.706
V	1+028.089	0.000	187.646	187.660
CL. BRG. N. ABUT.	1+030.196	0.000	187.617	187.623
BK. OF N. ABUT.	1+031.229	0.000	187.602	187.608

P. G. L.

LOCATION	STATION	OFFSET	THEORET. GRADE EL.	THEORET. GRADE EL. ADJ. FOR DEAD LOAD DEFLECTIONS AND GRINDING
BK. OF S. ABUT.	0+952.523	0.050	188.292	188.298
CL. BRG. S. ABUT.	0+953.556	0.050	188.284	188.290
A	0+956.556	0.050	188.259	188.272
B	0+959.556	0.050	188.234	188.252
C	0+962.556	0.050	188.209	188.229
D	0+965.556	0.050	188.184	188.200
CL. S. BRG. PIER 2	0+969.350	0.050	188.153	188.159
CL. PIER 2	0+969.539	0.050	188.151	188.157
CL. N. BRG. PIER 2	0+969.728	0.050	188.150	188.156
E	0+972.728	0.050	188.125	188.148
F	0+975.728	0.050	188.100	188.136
G	0+978.728	0.050	188.075	188.120
H	0+981.728	0.050	188.050	188.099
I	0+984.728	0.050	188.025	188.074
J	0+987.728	0.050	188.000	188.043
K	0+990.728	0.050	187.976	188.009
L	0+993.728	0.050	187.951	187.975
M	0+996.728	0.050	187.926	187.942
CL. PIER 1	1+001.052	0.050	187.890	187.896
N	1+004.052	0.050	187.865	187.871
O	1+007.052	0.050	187.840	187.850
P	1+010.052	0.050	187.815	187.832
Q	1+013.052	0.050	187.791	187.814
R	1+016.052	0.050	187.766	187.794
S	1+019.052	0.050	187.741	187.772
T	1+022.052	0.050	187.715	187.744
U	1+025.052	0.050	187.684	187.708
V	1+028.052	0.050	187.647	187.662
CL. BRG. N. ABUT.	1+030.159	0.050	187.618	187.624
BK. OF N. ABUT.	1+031.192	0.050	187.603	187.609

Notes:
See Sht. S5 for Elevations Location Plan.
All Elevations and Offsets are in meters.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TOP OF SLAB ELEVATIONS-III
CENTRAL AVENUE (F.A.U. RTE. 2798)
OVER
INTERSTATE 90 (KENNEDY EXPWY.) & C.T.A.
F.A.I. RTE. 90 SECTION: 1213B-1
COOK COUNTY STATION 1+000.000
STRUCTURE NO. 016-0659

SCALE: NONE *DRAWN BY: D.L./F.W.*
DATE: JANUARY 16, 2009 *CHECKED BY: B.N.S./J.C.N.*

CHRISTIAN-ROGE & ASSOC., INC.
CHICAGO *ILLINOIS*

\christroge elevation_3.dgn 1/19/2009 7:25:59 AM