

SUMMARY OF QUANTITIES			100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000-2A URBAN
CODE NO	ITEM	UNIT		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	51	51
40600300	AGGREGATE (PRIME COAT)	TON	255	255
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	50	50
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,010	1,010
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	69	69
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6,244	6,244
42001300	PROTECTIVE COAT	SQ YD	565	565
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	124	124
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,530	1,530
42400800	DETECTABLE WARNINGS	SQ FT	56	56
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	63,719	63,719
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	124	124
44000600	SIDEWALK REMOVAL	SQ FT	1,600	1,600
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,219	1,219
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	583	583
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	30	30
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	150	150
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	31	31
44213100	PAVEMENT FABRIC	SQ YD	181	181
44213200	SAW CUTS	FOOT	720	720
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	240	240
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	110	110
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	70	70
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	740	740
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	380	380
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	2,400	2,400
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	4,327	4,327
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	12	12
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	133	133
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	64	64
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	2	2

SUMMARY OF QUANTITIES			100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000-2A URBAN
CODE NO	ITEM	UNIT		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	33,000	33,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	764	764
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30,386	30,386
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,152	6,152
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	746	746
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	385	385
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	703	703
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	19,890	19,890
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	764	764
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30,386	30,386
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6,152	6,152
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	746	746
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	385	385
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	703	703
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,330	1,330
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	320	320
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	160	160
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,676	2,676
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1
Z0017202	DOWEL BARS 1 1/2"	EACH	200	200
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	139	139
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
o Z0076600	TRAINEES	HOUR	1000	1000

o 1080
NP - Non-participating
* SPECIALTY ITEM

FILE NAME = D168A50-sh-t-500.dgn
PLOT DATE = 1/8/2009



DESIGNED - D.L.
DRAWN - B.K.
CHECKED - M.P.
DATE - DECEMBER 1, 2008

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL RTE. 50 (CICERO AVENUE) SOUTH OF IL RTE. 19 TO EDENS EXPY.

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 12+17 TO STA. 118+57

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	2005-060 RS	COOK	30	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60A50	

Rev.