



POINTS ON IL. RTE. 50 (CICERO AVE.) ALIGNMENT

DESCRIPTION	STATION	NORTHING	EASTING
P. O. B.	10+00.00	4406.8855	4958.4652
P. O. T.	15+27.80	4934.6521	4952.4095
P. O. T.	15+27.80	4934.7324	4959.4090
P. C.	46+89.91	8096.6341	4923.1283
P. I.	47+37.25	8143.9671	4922.5852
P. T.	47+80.97	8181.2747	4951.7203
P. C.	49+81.80	8339.5645	5075.3357
P. I.	50+34.63	8381.1949	5107.8467
P. T.	50+78.22	8430.7793	5089.6414
P. C.	55+28.64	8851.3904	4928.5000
P. I.	55+52.86	8874.0016	4919.8374
P. T.	55+76.56	8898.2140	4919.5731
P. C.	68+74.89	10196.4665	4905.4029
P. I.	68+97.59	10219.1610	4905.1552
P. T.	69+20.03	10241.1760	4910.6729
P. C.	71+03.20	10418.8485	4955.2042
P. I.	71+43.34	10457.7864	4964.9635
P. T.	71+81.57	10496.2802	4953.5780
P. C.	73+13.67	10622.9514	4916.1118
P. I.	74+03.00	10708.6100	4890.7761
P. T.	74+91.26	10797.9188	4888.9785
P. O. T.	79+26.36	11232.9548	4881.3185
P. O. T.	84+10.56	11717.1229	4886.6469
P. O. T.	96+83.93	12990.4135	4872.3849
E. O. J.	119+38.20	15244.5758	4850.0893

CONTROL POINTS ON IL. RTE. 50 (CICERO AVE.)

PT. #	STATION	OFFSET	NORTHING	EASTING	DESC.
1	15+92.60	41.34	5000.0000	5000.0000	X-CUT
2	22+51.73	48.90	5659.1800	5000.0000	X-CUT
3	26+72.92	46.54	6080.3085	4992.8105	X-CUT
4	32+21.12	54.78	6628.4631	4985.7544	X-CUT
5	38+86.53	47.97	7293.8609	4980.3121	X-CUT
6	42+43.24	47.71	7650.5442	4975.9576	X-CUT
7	47+61.95	30.94	8150.0875	4967.9237	X-CUT
8	50+07.99	30.99	8350.4396	5117.1180	X-CUT
9	55+67.95	44.40	8892.9296	4964.2166	X-CUT
10	61+32.73	38.31	9454.7717	4951.8127	X-CUT
11	69+02.26	40.40	10217.9242	4947.2100	X-CUT
12	74+80.58	27.87	10788.2498	4917.1347	X-CUT
13	79+27.09	-24.40	11233.9509	4856.9286	X-CUT
14	88+03.99	-30.61	12110.1849	4851.6354	X-CUT
15	96+81.11	35.92	12987.9957	4908.3325	X-CUT
16	105+96.74	-35.93	13902.8230	4827.4239	X-CUT
17	110+25.15	42.09	14331.9854	4901.2103	I. P.
18	113+58.89	-42.12	14664.8745	4813.6974	X-CUT
19	14+70.82	-38.63	4877.2361	4914.4366	X-CUT
20	11+77.55	36.36	4584.8373	4992.7895	X-CUT
21	16+04.14	39.64	5011.5201	4998.1660	X-CUT
22	95+72.53	-39.85	12878.5776	4833.7842	X-CUT
23	86+26.55	61.71	11933.7903	4945.9378	X-CUT

FILE NAME = D162450-shr-ATB.dgn
PLOT DATE = 1/8/2009

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - D.L.
DRAWN - B.K.
CHECKED - M.P.
DATE - DECEMBER 1, 2008

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ALIGNMENT PLAN
IL. RTE. 50 (CICERO AVENUE) SOUTH OF IL. RTE. 19 TO EDENS EXPY.
SCALE: 1" = 100'
SHEET NO. 1 OF 1 SHEETS
STA. 12+17 TO STA. 118+57

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	2005-060 RS	COOK	30	6
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60A50	