



5 FT - COMB. CONC. CURB AND GUTTER REMOVAL AND REPLACEMENT

10 FT - COMB. CONC. CURB AND GUTTER REMOVAL AND REPLACEMENT

W. IRVING PARK ROAD

5 FT - COMB. CONC. CURB AND GUTTER REMOVAL AND REPLACEMENT

W. BERCEAU AVENUE

W. CULLOM AVENUE

W. BERCEAU AVENUE

W. HUTCHINSON STREET

HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"
 POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90, 1 3/4"
 POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50, 3/4"

BUTT JT. (TYP.)*

LEGEND

- EXISTING INLET
- EXISTING CATCH BASIN
- ⊙ EXISTING MANHOLE
- E CITY ELECTRIC
- W CITY WATER
- CE COM ED (ADJUSTMENTS PERFORMED BY OTHERS)
- T TELEPHONE (ADJUSTMENTS PERFORMED BY OTHERS)
- MWRD METROPOLITAN WATER RECLAMATION DISTRICT (ADJUSTMENTS PERFORMED BY OTHERS)
- G GAS
- ⊕ SP FRAMES AND LIDS TO BE ADJUSTED, SPECIAL
- C DRAINAGE STRUCTURES TO BE CLEANED
- ⊕ ADJ FRAMES AND LIDS TO BE ADJUSTED
- ⊕ REC DRAINAGE STRUCTURE TO BE RECONSTRUCTED

* SHALL BE PAID FOR AS "HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT"

FILE NAME = D160450-pla01.dgn
 PLOT DATE = 1/8/2009

CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - D.L.
 DRAWN - B.K.
 CHECKED - M.P.
 DATE - DECEMBER 1, 2008

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

ROADWAY PLAN
IL. RTE. 50 (CICERO AVENUE) SOUTH OF IL. RTE. 19 TO EDENS EXPY.
 SCALE: 1" = 50' SHEET NO. 1 OF 4 SHEETS STA. 10+00 TO STA. 38+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	2005-060 RS	COOK	30	7
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 60A50	