

**CONTRACT 60D21
RESURFACING SCHEDULE**

EASTBOUND

LOCATION		POLYMERIZED HMA SURFACE COURSE, SMA, N80	HMA SURFACE COURSE, MIX "D", N70	POLYMERIZED HMA BINDER COURSE, SMA, N80	HMA BINDER COURSE, IL-19, N70	POLYMERIZED LEVELING BINDER(MACHINE METHOD), IL- 4.75,N50	HMA SURFACE REMOVAL, 1 3/4"	HMA SURFACE REMOVAL, 3"	HMA SURFACE REMOVAL, 4"	HMA SURFACE REMOVAL, 4 1/4"	DESCRIPTION
STA	STA	(TON)	(TON)	(TON)	(TON)	(TON)	(SY)	(SY)	(SY)	(SY)	
485+91	500+00		168.8				1,722.1				OUTSIDE SHOULDER
500+00	512+36		140.0				1,428.4				OUTSIDE SHOULDER
513+63	517+88		50.9				519.1				OUTSIDE SHOULDER
524+00	531+05		100.8				1,028.3				OUTSIDE SHOULDER
531+98	568+58		436.8				4,457.5				OUTSIDE SHOULDER
572+63.1	579+41.6		73.9				753.9				OUTSIDE SHOULDER
583+08	592+26		115.0				1,173.1				OUTSIDE SHOULDER
593+30	604+23		105.0				1,071.3				OUTSIDE SHOULDER
606+05	607+28		25.5				259.7				OUTSIDE SHOULDER
485+91	569+04		582.8				5,947.1				INSIDE SHOULDER
572+45	580+00		57.5				587.2				INSIDE SHOULDER
583+06	607+28		278.7				2,843.9				INSIDE SHOULDER
GORE AREAS			201.0			8.0	1,887.8	142.7			
US 6 RAMP A			375.0			187.5		3,348.4			RAMPS & RAMP AREA
US 6 RAMP G			475.4			237.7		4,244.7			RAMPS & RAMP AREA
US 6 RAMP H			300.5			150.2		2,682.8			RAMPS & RAMP AREA
US 6 RAMP B			429.2			214.6		3,832.3			RAMPS & RAMP AREA
SIBLEY RAMP A			39.6		50.9				404.1		RAMPS & RAMP AREA
SIBLEY RAMP B			66.3		85.3				676.7		RAMPS & RAMP AREA
SIBLEY RAMP G			77.8		100.0				793.8		RAMPS & RAMP AREA
SIBLEY RAMP H			124.5		160.1				1,270.5		RAMPS & RAMP AREA
US 6 AREAS ADJACENT TO RAMPS			170.5			85.2		1,522.2			
485+91	568+55	4,110.4		4,110.4		1,461.5				34,797.4	MAINLINE
573+21	579+41	301.1		301.1		107.1				2,548.9	MAINLINE
583+42	607+28	1,181.4		1,181.4		420.0				10,001.1	MAINLINE
TAPERED AREA		147.7		147.7		52.5				1,250.5	MAINLINE
AUXILIARY LANES		138.4		138.4		49.2				1,171.9	MAINLINE
DEDUCTION				(20.8)							FOR BUTT JOINT
SUBTOTAL		5,879.1	4,395.4	5,858.2	396.3	2,973.6	23,679.4	15,773.1	3,145.1	49,769.8	
ROUNDED SUBTOTAL		5,880	4,396	5,859	397	2,974	23,680	15,774	3,146	49,770	

WESTBOUND

LOCATION		POLYMERIZED HMA SURFACE COURSE, SMA, N80	HMA SURFACE COURSE, MIX "D", N70	POLYMERIZED HMA BINDER COURSE, SMA, N80	HMA BINDER COURSE, IL-19, N70	POLYMERIZED LEVELING BINDER(MACHINE METHOD), IL- 4.75,N50	HMA SURFACE REMOVAL, 1 3/4"	HMA SURFACE REMOVAL, 3"	HMA SURFACE REMOVAL, 4"	HMA SURFACE REMOVAL, 4 1/4"	DESCRIPTION
STA	STA	(TON)	(TON)	(TON)	(TON)	(TON)	(SY)	(SY)	(SY)	(SY)	
485+91	515+39		342.0				3,489.7				OUTSIDE SHOULDER
515+39	569+15		605.2				6,175.0				OUTSIDE SHOULDER
573+18	579+75		85.8				875.9				OUTSIDE SHOULDER
583+43	607+28		267.0				2,724.4				OUTSIDE SHOULDER
485+91	569+04		693.5				7,076.2				INSIDE SHOULDER
572+45	580+00		65.8				671.1				INSIDE SHOULDER
583+06	607+28		355.6				3,628.7				INSIDE SHOULDER
GORE AREAS			146.1			11.1	1,264.9	197.9			
SHLDR AREAS			31.6				322.0				
US 6 RAMP E			438.4			219.2		3,914.4			RAMPS & RAMP AREA
US 6 RAMP C			417.7			208.8		3,729.4			RAMPS & RAMP AREA
US 6 RAMP D			392.9			196.5		3,508.4			RAMPS & RAMP AREA
US 6 Ramp F			218.1			109.1		1,947.7			RAMPS & RAMP AREA
SIBLEY RAMP C			67.1		86.3				685.1		RAMPS & RAMP AREA
SIBLEY RAMP D			114.4		147.0				1,167.0		RAMPS & RAMP AREA
SIBLEY RAMP E			46.2		59.4				471.2		RAMPS & RAMP AREA
SIBLEY RAMP F			62.8		80.8				641.0		RAMPS & RAMP AREA
US 6 AREAS ADJACENT TO RAMPS			136.2			68.1		1,216.5			
485+91	568+55	4,110.4		4,110.4		1,461.5				34,797.4	MAINLINE
573+21	579+41	301.1		301.1		107.1				2,548.9	MAINLINE
583+42	607+28	1,181.4		1,181.4		420.0				10,001.1	MAINLINE
TAPERED AREA		208.8		208.8		74.2				1,767.3	MAINLINE
AUXILIARY LANES		133.8		133.8		47.6				1,132.6	MAINLINE
DEDUCTION				(20.8)							FOR BUTT JOINT
SUBTOTAL		5,935.5	4,486.4	5,914.6	373.5	2,923.2	26,227.9	14,514.3	2,964.3	50,247.3	
ROUNDED SUBTOTAL		5,936	4,487	5,915	374	2,924	26,228	14,515	2,965	50,248	

TOTAL	11,816	8,883	11,774	771	5,898	49,908	30,289	6,111	100,018
-------	--------	-------	--------	-----	-------	--------	--------	-------	---------

FILE NAME = D168021-014-SCHEDULE.dgn	USER NAME = dwozmarski	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BISHOP FORD EXPRESSWAY (I-94) SCHEDULES OF QUANTITIES	F.A.I. RTE. 94	SECTION (0405,ETC,42-7&0707RS-11)	COUNTY COOK	TOTAL SHEETS 133	SHEET NO. 14	
PLOT SCALE = N/A	CHECKED -	REVISED -	SCALE: N/A			SHEET NO. 4 OF 7 SHEETS	STA.	TO STA.	CONTRACT NO. 60D21		
PLOT DATE = 2/6/2009	DATE - 2/6/2009	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								