

SUMMARY OF QUANTITIES				URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY		ROADWAY 1000-2A
20201006	GRADING AND SHAPING SHOULDERS	UNIT	40		40
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	25		25
40600300	AGGREGATE (PRIME COAT)	TON	125		125
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	35		35
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10		10
40600895	CONSTRUCTING TEST STRIP	EACH	2		2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	140		140
40600990	TEMPORARY RAMP	SQ YD	230		230
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,090		3,090
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	30,580		30,580
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50		50
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	200		200
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	250		250
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	620		620
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	170		170
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 24"	EACH	1		1
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	750		750
60262700	INLETS TO BE RECONSTRUCTED	EACH	2		2
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	24		24
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6
67100100	MOBILIZATION	L SUM	1		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1

\* DENOTES SPECIALTY ITEM  
NP = Non-participating

SUMMARY OF QUANTITIES				URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY		ROADWAY 1000-2A
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	550		550
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	225		225
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	53,100		53,100
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,050		1,050
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	150		150
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	600		600
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6,600		6,600
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	75		75
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17,700		17,700
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	350		350
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	50		50
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200		200
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	420		420
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	179		179
* 81400200	HEAVY-DUTY HANDHOLE	EACH	1		1
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,000		1,000
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1		1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52		52
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	1		1
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,330		1,330
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	61		61

FILE NAME = N:\PROJECTS\3329\3329\_37\Design\ProposedPlan\3329\_37-03-Quantities.dgn



**Ciiorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = e1au	DESIGNED - EPS	REVISED -
	DRAWN - MLB	REVISED -
PLOT SCALE = 1:0000' / IN.	CHECKED - WBL	REVISED -
PLOT DATE = 1/13/2009	DATE - 1/13/2009	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 53  
ST. CHARLES ROAD TO MADISON STREET  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
870	533 X-RS-4		18	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60E20	