


**SUMMARY OF QUANTITIES**

CODE	ITEM DESCRIPTION	UNIT	URBAN 100% FED. TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY	SAFTEY	BRIDGES		ELECTRICAL	
						J000-2A	SFTY-3N		26TH STREET OVER FRANKLIN CONNECTOR (SN 016-1064) X231-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	56	56					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	38	38					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	8	8					
20400800	FURNISHED EXCAVATION	CU YD	72	72					
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,945			1,100	845		
20800150	TRENCH BACKFILL	CU YD	40	40					
25000210	SEEDING, CLASS 2A	ACRE	0.05	0.05					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5	5					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5	5					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5	5					
25100115	MULCH, METHOD 2	ACRE	0.05	0.05					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	44	44					
28000400	PERIMETER EROSION BARRIER	FOOT	231	231					
28000510	INLET FILTERS	EACH	5	5					
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	117	117					
31101800	SUB-BASE GRANULAR MATERIAL, TYPE B 10"	SQ YD	518	518					
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	239	239					
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	12	12					
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	0.1	0.1					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1.6	1.6					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	0.1	0.1					
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	251	251					
42001300	PROTECTIVE COAT	SQ YD	753	753					
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	267	267					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PPC)	SQ YD	117	117					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,064	1,064					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	138	138					
44000100	PAVEMENT REMOVAL	SQ YD	216	216					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	352	352					
44000600	SIDEWALK REMOVAL	SQ FT	1,042	1,042					
44000700	APPROACH SLAB REMOVAL	SQ YD	444	444					
44001980	CONCRETE BARRIER REMOVAL	FOOT	323	323					
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	320	320					
44004250	PAVED SHOULDER REMOVAL	SQ YD	239	239					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	83	83					

S00-01

FILE NAME = p:\2008\c\15800\cadd\Sheets\S00.1.dgn	DESIGNED - TAI	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>		F.A.P. 392 FRANKLIN CONNECTOR (AT 26th STREET AND AT I-55 FRONTAGE ROAD B)		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - TAI	REVISED -					392	1717.2-3B-R	COOK	114	4
PLT DATE = 1/12/2009	CHECKED - TWB	REVISED -					SUMMARY OF QUANTITIES				
	DATE - 01/13/09	REVISED -					SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.				
							CONTRACT NO. 62197				
							FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				