

SUMMARY OF QUANTITIES

CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				ROADWAY	SAFTEY	BRIDGES		ELECTRICAL
						26TH STREET OVER FRANKLIN CONNECTOR (SN 016-1064)	FRONTAGE ROAD B OVER FRANKLIN CONNECTOR (SN 016-1093)	
				J000-2A	SFTY-3N	X231-2A	X231-2A	Y030-1E
* 81300100	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 4" X 4" X 3"	EACH	20					20
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	3	3				
* 81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO.10	FOOT	2,650					2,650
* 81900200	TRENCH AND BACKFILL ^{FOR} ELECTRICAL WORK	FOOT	80					80
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	8					8
* 82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	20					20
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	7					7
* 84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	1					1
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	1					1
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1					1
* 89502300	REMOVE ELECTRICAL CABLE FROM CONDUIT	FOOT	1,450					1,450
550A0030	STORM SEWERS, CLASS A, TYPE 1 8"	FOOT	54	54				
X0320870	BRACED EXCAVATION	CU YD	960				960	
* X0321478	MAINTENANCE OF EXISTING LIGHTING SYSTEM COMPLETE	L SUM	1					1
X0321866	REMOVE, STORE AND RE-ERECT SIGN PANEL	SQ FT	17	17				
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	6			4	2	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	4,788			4,788		
* X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	201			191	10	
X0300770	MANHOLES, TYPE A, 3'-DIAMETER, TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	2	1		1		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	426	426				
X0322927	BIKE LANE SYMBOL (CITY OF CHICAGO)	EACH	7	7				
X0712400	TEMPORARY PAVEMENT	SQ YD	27	27				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
* X8040150	REMOVAL OF ELECTRICAL CONNECTION TO SIGN STRUCTURE	EACH	1					1
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	900					900
* X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	L SUM	1					1
* X8360105	LIGHT POLE FOUNDATION, INTEGRAL WITH BARRIER WALL, 24" DIAMETER	FOOT	36					36
* 82107300	REMOVE EXISTING UNDERPASS LUMINAIRE, AND SALVAGE	EACH	8					8
* B4200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	19					19
* X8440120	REMOVE AND RE-ERECT EXISTING LIGHTING UNIT	EACH	10					10
XX005656	INLET FILTER CLEANING	EACH	5	5				
42400800	DETECTABLE WARNINGS	SQ FT	60	60				
* XX006937	GROUND ROD, 5/8" ^{DIA.} X 10 FT.	EACH	1					1

*Specialty Items

S00-04

FILE NAME = p:\2008\c\15800\Cadd\Sheet\S00-1.dgn	DESIGNED - TAI	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		F.A.P. 392 FRANKLIN CONNECTOR (AT 26th STREET AND AT I-55 FRONTAGE ROAD B)	F.A.P. RTE. 392	SECTION 1717.2-3B-R	COUNTY COOK	TOTAL SHEETS 114	SHEET NO. 7	
	DRAWN - TAI	REVISED -			SUMMARY OF QUANTITIES		CONTRACT NO. 62197		ILLINOIS FED. AID PROJECT		
PLGT. DATE = 1/12/2009	CHECKED - TWB	REVISED -									
	DATE - 01/13/09	REVISED -			SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.				