


PIER 3 (EAST FACE)
(Proposed pier modifications not shown)



PIER 4 (WEST FACE)
(Proposed pier modifications not shown)

NOTES:

- Repairs to piers shall be performed after completion of pier modifications and superstructure replacement.
- No repairs are intended to be made on the west face of Pier 3 or the east face of Pier 4.
- Cost of any additional concrete removal in spalled regions, including repair or replacement of damaged bars using an approved bar splicer or anchorage system, shall be included in "Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)."
- Bill of materials includes total quantities for repairs to both Pier 3 and Pier 4.

BILL OF MATERIAL

Item	Unit	Quantity
Epoxy Crack Injection	Foot	24
Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)	Sq. Ft.	10

Estimated quantities shown are based on field inspection performed in 2007. Actual quantities may be adjusted by the Engineer and will be paid for at the contract unit price.

LEGEND:

- Structural Repair of Concrete (Depth Equal to or Less Than 5 Inches)
- Epoxy Crack Injection
- Hairline Crack (Not to be injected)