F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2021.18-R	COOK	101	008
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62532

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	100% FED. URBAN X771-2A TOTAL QUANTITY	ROADWAY	BRIDGE (1)	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS						
					CONSTRUCTION TYPE CODE										
*	88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2					2						
*	88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	12					12						
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2					2						
□	X0320080	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	FOOT	1925					1925						
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	237	237										
*	X0322679	CONCRETE FOUNDATION FOR TYPE "P" BASE MOUNTED TRAFFIC SIGNAL CONTROLLER	EACH	2					2						
*	X0322683	CONCRETE FOUNDATION 24" DIA.	FOOT	72				27	45						
*	X0322684	CONCRETE FOUNDATION 30" DIA.	FOOT	22					22						
*	X0322701	SERVICE INSTALLATION, 100 AMP	EACH	1				1							
*	X0322712	STREET NAME SIGN	EACH	7					7						
	X0323080	DRAINAGE SCUPPERS, DS-12	EACH	6		6									
	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	8			8								
	X0324182	ELECTRICAL CABLE IN CONDUIT, TRIPLEX NO.6, 2-1C AND NO.8, 1-1C	FOOT	1550				1550							
	X0324571	MAINTENANCE OF STREET LIGHTING SYSTEM (CITY OF CHICAGO)	L SUM	1				1							
	X0324900	SERVICE CONNECTION TO CECO LINE	EACH	1				1							
	X0324902	REMOVE EXISTING TRAFFIC SIGNAL FOUNDATION	EACH	7					7						
	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	12			12								
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	2223		2223									
*	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	510				510							
*	X0329888	REMOVE EXISTING STREET LIGHTING EQUIPMENT	L SUM	1				1							
*	X0329890	SOLID STATE FULL-ACTUATED CONTROLLER, 4-PHASE DIGITAL TIMING WITH SOLID STATE TIME BASE COORDINATOR IN BASE MOUNTED CABINET	EACH	2					2						
*	81012600	CONDUIT IN TRENCH 2" DIA., PVC	FOOT	1100				1100							
*	81012800	CONDUIT IN TRENCH 3" DIA., PVC	FOOT	112					112						
*	8101300	CONDUIT IN TRENCH 4" DIA., PVC	FOOT	151					151						
*	X0934800	MAST ARM, STEEL, MONOTUBE 20 FT.	EACH	3					3						
*	X0934900	MAST ARM, STEEL, MONOTUBE 26 FT.	EACH	2					2						
*	X0935100	MAST ARM, STEEL, MONOTUBE 35 FT.	EACH	2					2						
*	X0935700	ELECTRIC CABLE IN CONDUIT NO. 12 19/C	FOOT	1087					1087						
*	X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1					1						
*	X0966510	SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, FIBER OPTIC, MAST ARM MOUNTED	EACH	4					4						
*	X0966520	SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, FIBER OPTIC, BRACKET MOUNTED	EACH	4					4						

* DENOTES SPECIALTY ITEMS
□ NON-PARTICIPATING

BRIDGE INFORMATION

① 111TH ST. OVER NB & SB I-57 S.N. 016-0989

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
111TH STREET OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/16/09 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\TTBOXMRAJGN...\SU000UEJDGN...\SU030UH9JDGN
H:6-2009.1054426 T:\DOCUMENTS\93086GN\CIVIL\DGN\SU000UD.DGN
HECHTBR