F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2021.1B-R	COOK	101	009
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 62532				

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	100% FED URBAN X771-2A TOTAL QUANTITY	ROADWAY	BRIDGE (1)	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS	CONSTRUCTION TYPE CODE
*	X0966700	JUNCTION BOX, POLE OR POST MOUNTED	EACH	10					10	
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
*	X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1				1		
*	X0323157	REMOVE LUMINAIRE FROM UNDERPASS	EACH	12			12			
	XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	418	418					
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5				
□	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15					
	Z0018800	DRAINAGE SYSTEM	L SUM	1		1				
	Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	30				15	15	
	Z0030240	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2					
	Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4					
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
	Z0064800	SELECTIVE CLEARING	UNIT	1	1					
	Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1		1				
⊙	Z0076600	TRAINEES	HOUR	1,000	1,000					
*	81900302	TRENCH AND BACKFILL WITH SCREENINGS OR SAND	FOOT	1314			214	1100		
*	84200700	LIGHTING FOUNDATION REMOVAL	EACH	3				3		
*	81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	950					950	
*	X0326347	ELECTRIC CABLE IN CONDUIT NO. 4 2 C	FOOT	195					195	
*	87301155	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 7 C	FOOT	575					575	
*	81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	150				150		
*	X8250085	LIGHTING CONTROLLER, DUPLEX CONSOLE TYPE	EACH	1				1		
*	X8300100	LIGHT POLE, ALUMINUM, WITH MAST ARM, INSTALL ONLY	EACH	15				15		
*	82107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	12			12			
*	X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	L SUM	1			1			
*	81028080	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT, 3"	FOOT	948					948	
*	X8210407	LUMINAIRE, INSTALL ONLY	EACH	19			19			

⊙ Y080

* DENOTES SPECIALTY ITEMS

□ NON-PARTICIPATING

BRIDGE INFORMATION

① 111TH ST. OVER NB & SB I-57 S.N. 016-0989

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
111TH STREET OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH

DATE: 01/16/09 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\TB0XMM4.DGN ..\SU0000UR.DGN ..\SU0000UR.DGN
I-66-2009 10:54:27 I:\UDCUMENTS\0580660P\CIVIL\UGRN\SU0004.UU: N
MECHTB1