

SIDEWALK REMOVAL				
FROM STATION	TO STATION	SQ FT	LOCATION	SQ FT
10+15.74	10+06.46	93.2	SW CORNER 111 & MARSHFIELD	93.2
10+56.39	10+43.95	99.4	NW CORNER 111 & MARSHFIELD	99.4
10+69.99	10+96.96	211.0	SE CORNER 111 & MARSHFIELD	211.0
11+01.19	11+18.83	218.8	NE CORNER 111 & MARSHFIELD	218.8
12+73.09	13+23.31	468.6	SW CORNER 111 & HAMLET	468.6
12+93.26	13+57.75	459.9	NW CORNER 111 & HAMLET	459.9
14+05.03	14+24.45	143.8	NE CORNER 111 & HAMLET	143.8
13+70.38	13+92.00	264.9	SE CORNER 111 & HAMLET	264.9
TOTAL=				1960

APPROACH SLAB REMOVAL			
FROM STATION	TO STATION	SQ FT	SQ YD
10+85.25	11+05.25	1366.7	151.9
12+81.82	13+11.38	1942.4	215.8
TOTAL=			368

STRIP REFLECTIVE CRACK CONTROL TREATMENT				
FROM STATION	TO STATION	SQ FT	LOCATION	FOOT
9+96.26	11+09.05	112.8	MARSHFIELD AVE	225.6
0+00.00	0+43.24	43.2	RAMP D	86.5
9+00.00	11+23.13	223.1	HAMLET AVE	446.3
0+00.00	0+42.23	42.2	RAMP C	84.5
TOTAL=				843

TELESCOPING STEEL SIGN SUPPORT			
LOCATION	STATION	OFFSET	FOOT
MARSHFIELD	10+44.00	RT	13.0
RAMP C	0+03.00	LT	13.0
RAMP D	1+25	RT	16.50
TOTAL=			43

BASE FOR TELESCOPING SIGN SUPPORT			
LOCATION	STATION	OFFSET	FOOT
MARSHFIELD	10+44.00	RT	1.0
RAMP C	0+03.00	LT	1.0
TOTAL=			2

THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS				
LOCATION	DESCRIPTION	SQ FT	SIZE	SQ FT
SB RAMP D	RT THRU ARROW	14.70	SMALL	14.7
SB RAMP D	THRU ARROW	6.50	SMALL	6.5
SB RAMP D	LEFT ARROW	8.80	SMALL	8.8
HAMLET AVE	LT ARROW ONLY	20.60	SMALL	20.6
HAMLET AVE	RT ARROW ONLY	20.60	SMALL	20.6
TOTAL=				71

THERMOPLASTIC PAVEMENT MARKING - LINE 4"						
LOCATION	FROM STATION	TO STATION	SKIP DASH	COLOR	LANES	FOOT
RAMP D	0+16.66	0+43.24	N/A	WHITE		26.6
RAMP D	0+27.95	0+43.24	N/A	YELLOW		15.3
RAMP C	0+00.00	0+42.23	N/A	YELLOW		42.2
RAMP C	0+31.81	0+42.23	N/A	WHITE		10.4
HAMLET AVE	9+00.00	10+31.87	N/A	YELLOW		131.9
MARSHFIELD AVE	10+30.77	10+47.66	N/A	YELLOW		16.9
MEDIAN W. R.R.	8+83.12	9+70.60	N/A	YELLOW		513.9
MEDIAN E. R.R.	9+93.51	10+20.08	N/A	YELLOW		137.6
MEDIAN HAMLET/111TH	14+14.24	15+93.00	N/A	YELLOW		711.6
HAMLET AVE	9+00.00	9+40.00	6'-18'	WHITE	2.00	20.0
RAILROAD DIAGONALS				WHITE		230.0
TOTAL=						1856

THERMOPLASTIC PAVEMENT MARKING - LINE 6"					
LOCATION	FROM STATION	TO STATION	FOOT	LANES	FOOT
RAMP D	0+22.28	0+43.24	21.0	2.0	41.9
HAMLET AVE	9+40.00	10+37.13	97.1	2.0	194.3
CROSSWALK MARSH/111TH			385.2		385.2
CROSSWALK HAMLET/112TH			103.6		103.6
TOTAL=					725

THERMOPLASTIC PAVEMENT MARKING - LINE 12"		
LOCATION	FOOT	
MEDIAN DIAGONALS MARSHFIELD/111TH	70.0	
MEDIAN DIAGONALS HAMLET/111TH	80.0	
CROSSWALK HAMLET/111TH	234.0	
RAILROAD STRIPE	18.0	
TOTAL=		402

TEMPORARY PAVEMENT MARKING- LETTERS AND SYMBOLS				
LOCATION	DESCRIPTION	SQ FT	LANES	SQ FT
WB 111TH AT HAMLET	RT TURN ARROW	15.2	2.0	30.4
EB 111TH AT MARSHFIELD AVE	RT TURN ARROW	15.2	2.0	30.4
TOTAL=				61

TEMPORARY PAVEMENT MARKING - LINE 4"		
LOCATION	FOOT	
MARSHFIELD RD NEXT TO TEMPORARY BARRIER WALL	272.0	
HAMLET AVE NEXT TO TEMPORARY BARRIER WALL	230.0	
TOTAL=		502

TEMPORARY PAVEMENT MARKING - LINE 6"			
FROM STATION	TO STATION	LOCATION	FOOT
14+14.55	15+72.98	WB 111TH	158.4
8+15.02	9+35.56	EB 111TH	120.5
		MARSHFIELD RD	270.0
		CONCRETE BARRIER WALL	270.0
		OUTSIDE SB I-57	270.0
		CONCRETE BARRIER WALL	290.0
		INSIDE SB I-57	270.0
		CONCRETE BARRIER WALL	270.0
		INSIDE NB I-57	270.0
		CONCRETE BARRIER WALL	270.0
		OUTSIDE NB I-57	270.0
		CONCRETE BARRIER WALL	230.0
		HAMELET AVE	230.0
TOTAL=			1879

WORK ZONE PAVEMENT MARKING REMOVAL		
PAY ITEM #	PAY ITEM	SQ FT
70300100	SHORT-TERM PAVEMENT MARKING	73.9
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	61.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	165.7
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	939.5
TOTAL=		1240

TEMPORARY CONCRETE BARRIER		
LOCATION	FOOT	
MARSHFIELD RD	270.0	
OUTSIDE SB I-57	270.0	
INSIDE SB I-57	290.0	
INSIDE NB I-57	270.0	
OUTSIDE NB I-57	270.0	
HAMELET AVE	230.0	
TOTAL=		1600

THERMOPLASTIC PAVEMENT MARKING - LINE 24"		
LOCATION	STATION	FOOT
SB RAMP D	0+46.41	40.0
NB HAMLET AVE	16+03.92	41.0
EB 111TH	9+40.05	17.5
WB 111TH	10+17.21	17.5
WB 111TH	14+30.05	13.5
TOTAL=		130

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS					
LOCATION	DESCRIPTION	SQ FT	SIZE	LANES	SQ FT
WB 111TH BRIDGE	R.R. CROSSING	61.2	LARGE	1	61.2
EB 111TH STREET	R.R. CROSSING	61.2	LARGE	1	61.2
WB 111TH BRIDGE	LT ARROW ONLY	20.6	SMALL	2	41.2
EB 111TH BRIDGE	LT ARROW ONLY	20.6	SMALL	2	41.2
TOTAL=					205

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
111TH STREET OVER
F.A.I. ROUTE 57 (INTERSTATE 57)

SCHEDULE OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/16/09 CHECKED BY: ACL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE., CHICAGO, IL 60601
TELEPHONE: 312/416-0000

\\TTB00M\ALD0N\1\SC00001P.DGN
 1-16-2009 10:42:50
 T:\DOCUMENT\230806\1\CIVIL\ALD0N\SC00001P.DGN
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63
 HECHTER